



034115

PHOSPHORUS

Lambda User Controlled Infrastructure for European Research

Integrated Project

Strategic objective: Research Networking Test-beds



Deliverable reference number: D.2.4

Report on Grid-GMPLS Control Plane functional tests

Due date of deliverable: 2008-07-31 Actual submission date: 2008-07-31 Document code: Phosphorus-WP2-D2.4

Start date of project:
October 1, 2006

Duration:
30 Months

Organisation name of lead contractor for this deliverable: **Poznan Supercomputing and Networking Center** (PSNC)

Project co-funded by the European Commission within the Sixth Framework Programme (2002-2006)						
	Dissemination Level					
PU	Public	✓				
PP	Restricted to other programme participants (including the Commission Services)					
RE	Restricted to a group specified by the consortium (including the Commission Services)					
СО	Confidential, only for members of the consortium (including the Commission Services)					



Abstract

This deliverable presents functional tests on G²MPLS Control Plane prototype, which were performed in some local test-bed deployed in Phosphorus project (specifically , PSNC and UESSEX local test-beds). These tests validate the whole G²MPLS software stack acting the role of network core controller, network border controller and provider edge controller. They also check the expected functionalities of every software component implemented into the stack.



Table of Contents

0	Exec	7		
1	Obje	8		
2	Term	inology		9
3	Testi	ng enviro	onment	10
	3.1	Trans	port Plane	10
		3.1.1	Equipment	10
		3.1.2	Physical topology	12
	3.2	Contro	ol Plane	20
	3.3	G ² MP	LS Control Plane configuration	21
4	Testi	ng metho	odology	23
5	G ² MF	PLS Cont	trol Plane functional tests	25
	5.1	Overv	iew of the tests	25
	5.2	LSP s	ignalling tests	26
		5.2.1	LSP signalling tests in LSC domain	27
		5.2.2	LSP signalling tests in FSC domain	47
	5.3	G ² MP	LS call signalling tests	66
		5.3.1	Single-domain call signalling tests	66
		5.3.2	Inter-domain call signalling tests	82
	5.4	G ² MP	LS routing tests	89
		5.4.1	Single-domain routing test-cases	89
		5.4.2	Inter-domain routing test cases	97
6	Conc	lusions		104
7	Refe	rences		105

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



8 Acronyms 106

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



List of Figures

Figure 3.1: Adva FSP 3000RE-II	11
Figure 3.2: Calient Diamond Wave Fiber Connect	12
Figure 3.3: UESSEX fibre switching test-bed topology.	13
Figure 3.4 Calient interfaces and G ² MPLS identifiers in UESSEX testbed	14
Figure 3.5 PSNC fibre switching test-bed topology	15
Figure 3.6: PSNC wavelength switching test-bed topology	19
Figure 3.7: A G ² MPLS Control Plane configuration	22
Figure 5.1: Logical topology of the single-domain LSC test-bed	27
Figure 5.2: Logical topology of the single-domain FSC test-bed	48
Figure 5.3: Logical topology of the single-domain FSC test-bed for G2MPLS Call signalling tests	67
Figure 5.4: Logical topology of the inter-domain FSC test-bed for G ² MPLS Call signalling tests	83
Figure 5.5: Single-domain logical topology for routing tests	90
Figure 5.6: Inter-domain logical topology for routing tests	

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



List of Tables

Table 3.1 Summary of available equipments in PSNC and UESSEX domains for G ² MPLS functional tests	. 11
Table 3.2 Calient interfaces and G ² MPLS identifiers in PSNC test-bed	
Table 3.3 ADVA interfaces capabilities, configuration and G ² MPLS identifiers	20
Table 5.1 Overview of the executed test-cards.	26

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



• Executive Summary

This document reports the G²MPLS Control Plane prototype functional tests. The purpose of these tests is to verify the Grid and network functionalities implemented in software prototype.

The actual scope of the document is stated in section 1, which provides the guiding information on how to read and use the whole document.

Section 2 introduces into the used terminology and refers to the acronyms list in section 8.

Section 3 describes the testing environment in terms of both transport plane resources and Control Plane configurations to control these resources.

Section 4 introduces testing methodology that has been used for tests descriptions.

Sections 5 presents functional tests and it is divided in three main areas of G²MPLS functionalities:

- LSP signalling, mainly aimed to verify G²MPLS signalling protocol behaviours and related transport network configurations,
- single-domain and inter-domain G²MPLS call signalling, mainly focused on higher level G²MPLS signalling controllers (NCC, CCC) and related interfaces,
- single-domain and inter-domain G²MPLS routing, mainly aimed to check the Grid and Network information advertisement by routing module.

Finally, in section 6 some concluding remarks are provided.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Objectives and Scope

This deliverable only provides the information and the results with regards to functional testing on the different modules implemented for the GMPLS and G²MPLS Control Plane. The work reported here is supported by WP2 design documents concerning the G²MPLS architecture [PH-WP2-D2.1] and deployment models [PH-WP2-D2.6], the protocol extensions [PH-WP2-D2.2], the interfaces [PH-WP2-D2.7] and the high-level software design [PH-WP2-D2.3].

This document reports on the specific functional tests conducted to identify and confirms the proper operation of the various G²MPLS modules (developed from scratch or modified with respect to the Quagga software baseline) on real equipments deployed in some Phosphorus local test-beds (fiber and wavelength switches). The deliverable includes:

- The testing environment used to check the performance of the G²MPLS Control Plane software, which focuses on the Transport Plane including equipment and physical topology, as well as on the Control Plane with its G²MPLS stack configuration.
- The methodology for all the conducted tests, introduced to help the reader in following the testing. This methodology is based on a table representing the test-card model used for each test. It describes the objectives of the test and its relationships with other tests carried out. Each test is performed in a step by step basis, checking the correct functioning with the expected results. Finally, a test status confirmation is added to report the test result.
- The actual G²MPLS Control Plane functional tests are been logically reported under three main sections; the LSP signalling tests, the call signalling tests and the routing tests.

This deliverable provides also a general reference to any potential user of the G²MPLS software, in terms of network environment to be created (both physical and logical topologies) and tests to be run for the early checking of the G²MPLS functionalities. The reference to the specific Transport Plane hardware used in the used local Phosphorus test-bed (i.e. ADVA FSP 3000RE-II wavelength switches and Calient Diamondwave Fiber Connect switches) does not limit the scope of the test suite described in this document, but rather suggests a testing methodology for any possible further development by G²MPLS users.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Terminology

No specific terminology is introduced by this document. Please refer to Deliverable [PH-WP2-D2.1], [PH-WP2-D2.2], [PH-WP2-D2.3], [PH-WP2-D2.6] and [PH-WP2-D2.7] for any specific terms used.

A full list of the abbreviations used in this document is provided in Section 8.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3 Testing environment

This section describes the testing environment used to test the functionalities of the G²MPLS Control Plane software, focusing on the physical topology, the Control Plane and the G²MPLS stack configuration.

3.1 Transport Plane

This section reports the details of the PSNC and UESSEX test-beds used for the G²MPLS Control Plane test. One fibre switched test-bed from UESSEX, one fibre switched test-bed from PSNC and one wavelength switched test-bed from PSNC were involved in the test. Details of the test-beds and the involved equipments are described in the following sections.

3.1.1 Equipment

Table 3.1 shows equipment inventory in PSNC and UESSEX local test-beds.

EQUIPMENT							
	PSNC		UESSEX				
Type/Make/ Model	No.	Attrib.	Type Make/Model	No.	Attrib.		
ADVA FSP 3000RE-II (Lambda	3	15 Pass through ports	CalientDiamondWav e (Fibre Switch)	1 (4 after	96 ports total		
Switch)		6 Local ports	e (Fibre Switch)	partitioning)			
CalientDiamond Wave (Fibre Switch)	1 (4 after partitioning)	144 ports total	VLAN capable GE switch (FastIronFoundry)	1	24 ports optical		
VLAN capable GE switch (XMR Foundry)	1	60 ports	VPN Gateway	1			
Equipment controller	7	Virtualized PC	Equipment Controller	4	PCs		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Client nodes	2	HP IA64 2xIntel Itanium2 servers	Client nodes	2	Intel dual core processor servers
Traffic Analyser/Gener ator (Agilent)	1	2X10GE 2x1GE	Traffic Analyser/Generator (Anritsu)	1	10GE network analyser

Table 3.1 Summary of available equipments in PSNC and UESSEX domains for G²MPLS functional tests.

3.1.1.1 LSC equipment - ADVA FSP 3000RE-II

There are three ADVA FSP 3000RE-II switches available in PSNC domain test-bed. They are lambda switches with add/drop capability through their local I/O (ROADM) as indicated in the following picture.




Figure 3.1: Adva FSP 3000RE-II.

3.1.1.2 FSC equipment - Calient Diamond Wave Fibre Connect

There is one Calient switch available in PSNC domain test-bed and one Calient switch in UESSEX domain. They are both a fiber switch and have been configured in a similar way. Each fiber switch has been partitioned as four individual sub-switches. Therefore each test-bed and domain resulted in four individual fibre switches.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115






Figure 3.2: Calient Diamond Wave Fiber Connect.

3.1.1.3 VLAN capable GE switches

Transport Plane in UESSEX and PSNC domains is supported by two Foundry GE switches (Foundry FastIron in UESSEX and Foundry XMR in PSNC). These switches facilitate the VLAN inter-domain connectivity between UESSEX and PSNC (through GEANT). Furthermore the provide connectivity between test-clients and traffic generators with the test-bed in each domain. Therefore, they are completely transparent for the G²MPLS Control Plane and are used just to emulate connectivity to the main switching domains (LSC and FSC).

3.1.2 Physical topology

The aforementioned equipments and facilities were used to build two test-beds in PSNC and UESSEX for the Control Plane functionality test. Topologies of these test-beds are described below:

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.1.2.1 UESSEX fibre switched test-bed topology




Figure 3.3: UESSEX fibre switching test-bed topology.

The test-bed comprises one Calient Diamondwave Fiber Connect as the optical fibre-switching node. To emulate functionality of a realistic network with multiple optical switching nodes, the Calient switch has been partitioned into four independent sub- switches (i.e. Calient_1, Calient_2, Calient_3 and, Calient_4). This has been done through a proprietary software interface jointly developed by UESSEX and PSNC. Through the software interface, the Control Plane interfaces to four switches that can be communicated and operated independently. The four switches are interconnected with bi-directional optical fibres in a fully meshed topology. As shown in Figure 3.3, there is one direct bi-directional path between each two nodes. In the test-bed, each switch is controlled by a G²MPLS node controller, which is an Intel quad core server and runs an instance of the G²MPLS Control Plane. These four nodes are connected through the 1GE local area network, which constitute the Signalling Control Network (SCN) for the G²MPLS Control Plane. In this test-bed, the user's Transport Plane is emulated by an Anritsu traffic analyser/generator. Each user uses one sink-source port of the traffic generator to transmit-receive data with optical 10GE format. For each user, there is an Inter dual core

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



server that runs the G.UNI signalling and is connected to the SCN. Figure 3.3 shows topology of the test-bed and its physical layer connectivity together with associated IP addresses, port numbers and fibre numbers.

Virtual Switch Name	interface ID	Equip ID	Board ID	Port ID	TN direction	Remote interface ID
Calient_1	1.1.1	0x1	0x1	0x1101	Local I/O	S4.P1
	1.1.3	0x1	0x1	0x1103	Local I/O	S4.P2
	1.2.1	0x1	0x1	0x1201	To Calient_2	2.1.1
	1.3.1	0x1	0x1	0x1301	To Calient_3	3.1.1
	1.4.1	0x1	0x1	0x1401	To Calient_4	4.1.1
Calient_2	2.1.1	0x1	0x1	0x2101	To Calient_1	1.2.1
	2.3.1	0x1	0x1	0x2301	To Calient_3	2.3.2
	2.4.1	0x1	0x1	0x2401	To Calient_4	2.4.1
Calient_3	3.1.1	0x1	0x1	0x3101	To Calient_1	1.3.1
	3.2.1	0x1	0x1	0x3201	To Calient_2	2.3.1
	3.3.1	0x1	0x1	0x3301	Local I/O	S5.P1
	3.3.3	0x1	0x1	0x3303	Local I/O	S5.P2
Calient_4	4.1.1	0x1	0x1	0x4101	To Calient_1	1.3.1
	4.2.1	0x1	0x1	0x4201	To Calient_2	2.3.1
	4.3.1	0x1	0x1	0x4301	To Calient_3	3.4.1

Figure 3.4 Calient interfaces and G²MPLS identifiers in UESSEX testbed.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.1.2.2 PSNC fibre switched test-bed topology




Figure 3.5 PSNC fibre switching test-bed topology.

The test-bed comprises one Calient Diamondwave Fiber Connect as the optical fibre-switching node. To emulate functionality of a realistic network with multiple optical switching nodes, the Calient switch was partitioned into four independent sub-switches, as in the UESSEX case. The four switches are connected with bi-directional optical fibres in a fully meshed topology. As shown in Figure 3.5, there is 2-6 direct bi-directional path between each two virtual nodes. More data links between virtual nodes give great possibility to setup a set of LSPs going through the same transport plane node or setup LSPs using two or more data links as component links. In the test-bed, each switch is controlled by a G²MPLS node controller (i.e. Calient controller 1..4), which is an Intel Itanium2 core server and runs an instance of the G²MPLS stack These four nodes are

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



connected through the local area network implementing the SCN. In this test-bed client nodes are emulated by a test client and a traffic analyser/generator. The client nodes are connected to the optical switches through a foundry XMR switch. Each client uses a range of VLAN tags as shown in Figure 3.5 to transmit-receive data with optical 1GEtherent format. Each VLAN tag is associated with fibre connectivity to one switching node. Each client also runs the client signalling or G.UNI and is connected to Control Plane network. Figure 3.4 and Table 3.2 shows topology of the test-bed and its physical layer connectivity together with associated IP addresses, port numbers, fibre numbers and its G²MPLS identifiers.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Virtual Switch	interface ID	Equip ID	Board ID	Port ID	TN direction	Remote interface ID
Name				0.1101	Less II/O	
Calient_1	1.1.1	0x1	0x1	0x1101	Local I/O	VLAN 201
	1.1.2	0x1	0x1	0x1102	Local I/O	VLAN 301
	1.2.1	0x1	0x1	0x1201	To Calient_2	2.1.1
	1.2.2	0x1	0x1	0x1202	To Calient_2	2.1.2
	1.2.3	0x1	0x1	0x1203	To Calient_2	2.1.3
	1.2.4	0x1	0x1	0x1204	To Calient_2	2.1.4
	1.2.5	0x1	0x1	0x1205	To Calient_2	2.1.5
	1.2.6	0x1	0x1	0x1206	To Calient_2	2.1.6
	1.3.1	0x1	0x1	0x1301	To Calient_3	3.1.1
	1.3.2	0x1	0x1	0x1302	To Calient_3	3.1.2
	1.3.3	0x1	0x1	0x1303	To Calient_3	3.1.3
	1.3.4	0x1	0x1	0x1304	To Calient_3	3.1.4
	1.3.5	0x1	0x1	0x1305	To Calient_3	3.1.5
	1.3.6	0x1	0x1	0x1306	To Calient_3	3.1.6
	1.4.1	0x1	0x1	0x1401	To Calient_4	4.1.1
	1.4.2	0x1	0x1	0x1402	To Calient_4	4.1.2
Virtual Switch Name	interface ID	Equip ID	Board ID	Port ID	TN direction	Remote interface ID
Calient_2	2.1.1	0x1	0x1	0x2101	To Calient_1	1.2.1
	2.1.2	0x1	0x1	0x2102	To Calient_1	1.2.2
	2.1.3	0x1	0x1	0x2103	To Calient_1	1.2.3
	2.1.4	0x1	0x1	0x2104	To Calient 1	1.2.4
		0/12	OXI	082104	10 Callent_1	1.2.4
	2.1.5	0x1	0x1	0x2104	To Callent_1	1.2.5
					_	
	2.1.5	0x1	0x1	0x2105	To Calient_1	1.2.5
	2.1.5 2.1.6	0x1 0x1	0x1 0x1	0x2105 0x1206	To Calient_1 To Calient_1	1.2.5 1.2.6
	2.1.5 2.1.6 2.2.1	0x1 0x1 0x1	0x1 0x1 0x1	0x2105 0x1206 0x2201	To Calient_1 To Calient_1 Local I/O	1.2.5 1.2.6 VLAN 202
	2.1.5 2.1.6 2.2.1 2.2.2	0x1 0x1 0x1 0x1	0x1 0x1 0x1 0x1	0x2105 0x1206 0x2201 0x2202	To Calient_1 To Calient_1 Local I/O Local I/O	1.2.5 1.2.6 VLAN 202 VLAN 302
	2.1.5 2.1.6 2.2.1 2.2.2 2.3.1	0x1 0x1 0x1 0x1 0x1	0x1 0x1 0x1 0x1 0x1	0x2105 0x1206 0x2201 0x2202 0x2301	To Calient_1 To Calient_1 Local I/O Local I/O To Calient_3	1.2.5 1.2.6 VLAN 202 VLAN 302 2.3.2

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



Virtual Switch Name	interface ID	Equip ID	Board ID	Port ID	TN direction	Remote interface ID
Calient_3	3.1.1	0x1	0x1	0x3101	To Calient_1	1.3.1
	3.1.2	0x1	0x1	0x3102	To Calient_1	1.3.2
	3.1.3	0x1	0x1	0x3103	To Calient_1	1.3.3
	3.1.4	0x1	0x1	0x3104	To Calient_1	1.3.4
	3.1.5	0x1	0x1	0x3105	To Calient_1	1.3.5
	3.1.6	0x1	0x1	0x3206	To Calient_1	1.3.6
	3.2.1	0x1	0x1	0x3201	To Calient_2	2.3.1
	3.2.2	0x1	0x1	0x3202	To Calient_2	2.3.2
	3.3.1	0x1	0x1	0x3301	Local I/O	VLAN 251
	3.3.2	0x1	0x1	0x3302	Local I/O	VLAN 353
	3.4.1	0x1	0x1	0x3401	To Calient_4	4.3.1
	3.4.2	0x1	0x1	0x3402	To Calient_4	4.3.2
Virtual Switch Name	interface ID	Equip ID	Board ID	Port ID	TN direction	Remote interface ID
Calient_4	4.1.1	0x1	0x1	0x4101	To Calient_1	1.3.1
	4.1.2	0x1	0x1	0x4102	To Calient_1	1.3.2
	4.2.1	0x1	0x1	0x4201	To Calient_2	2.3.1
	4.2.2	0x1	0x1	0x4202	To Calient_2	2.3.2
	4.3.1	0x1	0x1	0x4301	To Calient_3	3.4.1
	4.3.2	0x1	0x1	0x4302	To Calient_3	3.4.2
	4.4.1	0x1	0x1	0x4401	Local I/O	VLAN 252
	4.4.2	0x1	0x1	0x4402	Local I/O	VLAN 354

Table 3.2 Calient interfaces and G²MPLS identifiers in PSNC test-bed.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



3.1.2.3 PSNC wavelength switched test-bed topology




Figure 3.6: PSNC wavelength switching test-bed topology.

The test-bed comprises three ADVA FSP 3000RE-II wavelength switches as the optical wavelength-switching nodes (POZNAN, CRACOW, WARSAW). The ROADMs are connected with bi-directional optical fibres in a ring topology. In the test-bed, each optical switch is controlled by a G²MPLS node controller, which is an Intel quad core server. These three nodes are connected through the local area network implementing the SCN. In this test-bed client nodes are emulated by a test client and a traffic analyser/generator. The client nodes are connected to the optical switches through a foundry XMR switch. Each client uses a range of VLAN tags as shown in Figure 3.6 to transmit-receive data with optical 1GE format. Each VLAN tag is associated to a specific fibre connectivity to one switching node. Each client also runs the G.UNI signalling and is connected to the

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



SCN. Figure 3.6 and Table 3.3 show topology of the test-bed and its physical layer connectivity together with associated IP addresses, port numbers, fibre numbers and its G²MPLS identifiers.

Device Nar	ne	Manag addres	gement ss	TN	l interface ID	TN interface type		TN direction
Poznan		192.16	8.100.137	1.1	1.8	40λ-DWDM		To Warsow
					1.9	λ-1534.25nm		VLAN 201
				1.1	1.13	40λ-DWDM		To Cracow
				1.1	1.14	λ-1532.68nm		VLAN 202
Cracow		192.16	8.100.139	1.1	1.8	40λ-DWDM		To Poznan
				1.1	1.9	λ-1532.68nm		VLAN 302
				1.1	1.13	40λ-DWDM		To Warsow
				1.1	1.14	λ-1534.25nm		VLAN 301
				1.1	1.16	λ-1546.12nm		VLAN 203
Warsaw		192.16	8.100.138	1.1	1.8	40λ-DWDM		To Cracow
				1.1	1.9	λ-1546.12nm		VLAN 303
				1.1	1.13	40λ-DWDM		To Poznan
Device Name	TN interf	ace ID	Equip ID		Board ID	Port ID	L	abel ID(s)
Poznan	1.1.8		0.4					
			0x1		0x1	0x1108	Α	II ADVA labels
	1.1.9		0x1		0x1 0x1	0x1108 0x1109		All ADVA labels
	1.1.9 1.1.13	3			•		0	
			0x1		0x1	0x1109	0	x28000017
Cracow	1.1.13		0x1 0x1		0x1 0x1	0x1109 0x110D	0	x28000017 All ADVA labels
Cracow	1.1.13		0x1 0x1 0x1		0x1 0x1 0x1	0x1109 0x110D 0x110E	0	x28000017 All ADVA labels x28000019
Cracow	1.1.13 1.1.14 1.1.8	1	0x1 0x1 0x1 0x1		0x1 0x1 0x1 0x1	0x1109 0x110D 0x110E 0x1108	0	x28000017 All ADVA labels x28000019 All ADVA labels
Cracow	1.1.13 1.1.14 1.1.8 1.1.9	3	0x1 0x1 0x1 0x1 0x1		0x1 0x1 0x1 0x1 0x1	0x1109 0x110D 0x110E 0x1108 0x1109	000	0x28000017 All ADVA labels 0x28000019 All ADVA labels 0x28000019
Cracow	1.1.13 1.1.14 1.1.8 1.1.9 1.1.13	3	0x1 0x1 0x1 0x1 0x1 0x1		0x1 0x1 0x1 0x1 0x1 0x1	0x1109 0x110D 0x110E 0x1108 0x1109 0x110D	0 A 0 A 0	x28000017 All ADVA labels x28000019 All ADVA labels x28000019 All ADVA labels
Cracow	1.1.13 1.1.14 1.1.8 1.1.9 1.1.13 1.1.14	3	0x1 0x1 0x1 0x1 0x1 0x1 0x1		0x1 0x1 0x1 0x1 0x1 0x1 0x1	0x1109 0x110D 0x110E 0x1108 0x1109 0x110D 0x110D	0 A 0 A 0	x28000017 All ADVA labels x28000019 All ADVA labels x28000019 All ADVA labels x28000017
	1.1.13 1.1.14 1.1.8 1.1.9 1.1.13 1.1.14	3	0x1 0x1 0x1 0x1 0x1 0x1 0x1 0x1		0x1 0x1 0x1 0x1 0x1 0x1 0x1 0x1	0x1109 0x110D 0x110E 0x1108 0x1109 0x110D 0x110D 0x1110	0 A 0 A 0 0 A	x28000017 All ADVA labels x28000019 All ADVA labels x28000019 All ADVA labels x28000017 x28000008

Table 3.3 ADVA interfaces capabilities, configuration and G²MPLS identifiers.

3.2 Control Plane

The Control Plane is implemented by G²MPLS node controllers. Each controller operates exclusively (i.e. without concurrency with/of other control entities) on a Transport Network element (real or derived from partitioning) inside the boundaries of the G²MPLS domain. G²MPLS controllers run over i386 32bit platforms with Gentoo Linux distributions.

Each G²MPLS exposes at least an interface on the Signalling Communication Network (SCN) over which the G²MPLS protocol messages flow. In the single domain case IP tunnelling is used for out of band connectivity between controllers. Moreover, each G²MPLS controller is interfaced to the Transport Network equipment (Southbound interface for the Calient and ADVA devices) through TL1 connections across the same SCN. This

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



choices is not a requirement of the G²MPLS stack, but rather a simplification of addressing spaces in small sized domains in order to focus configuration and tests on the fundamental issues of the protocol behaviours.

3.3 **G²MPLS** Control Plane configuration

The configuration of the G²MPLS Control Plane for the testing environment requires the mapping of the actual physical topology into the proper configuration files associated with each of the G²MPLS processes. The default location of the configuration files is /usr/local/etc/.

Configuration files contain information like the vty login credentials or location of the log files. Moreover, the Irmd configuration file (Irmd.conf) sets the initial configuration of the node. Specifically, it configures the control interfaces, control channels, te-links and data-links, setting addresses and initial state. Figure 3.7 shows the network configuration example used for the tests described in the next sections.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115






Figure 3.7: A G²MPLS Control Plane configuration

The SCN in the test-bed is IP-based with private addressing. Router Ids and interfaces IP addresses are private IPv4 addresses as well.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



4 Testing methodology

The following table is the test-card model used for each test. Each of the cards has a set of fields to identify and describes the tests.

- Test Card Name, which briefly identifies the test;
- Authors, which identifies the team which has executed the test;
- Objective, which exposes the expected results of the performed test;
- Related Test Cards, which provides a list of the test cards that are related with the current test in terms
 of pre-requisite or imported common steps;
- Topology and DUT details, which depicts the topology and configuration used for the test;
- *Test description*, which reports the test in a step by step basis, checking the correct functioning and the results achieved are captured in the "Outcome" column;
- Additional comments, which reports any pre- and post-conditions of the test not previously included in the "Test description";
- Test status, which provides a test status confirmation to report if the test has been successful;

Test Card #	GMPLS-01	Authors						
Test Card Name	SPC test	Authors						
Objective								
Related Test Cards	<put a="" here="" if="" it="" list="" make="" sense=""></put>							
Topology and DUT details	<insert a="" an<="" p="" picture="" the="" topology="" with=""></insert>	<insert a="" and="" configuration,="" details="" dut="" for="" picture="" pre-requisites="" the="" topology="" with=""></insert>						

Test description					
Step	Description	Outcome			
1.					
1.1.					
1.1.1.					
1.1.2.					

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



2.	
3.	
4.	

Additional comments	
Some remarks, notes, but not configuration issues	
Test status	
Passed/Not passed	

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



G²MPLS Control Plane functional tests

5.1 Overview of the tests

The functionality of G^2MPLS Control Plane was tested using 35 test-cards divided into three main areas. Each test-card verifies a set of G^2MPLS features expressed as set of objectives to be achieved in the fixed environment conditions. All the test-cards have been successfully executed and thus the current state of the G^2MPLS Control Plane prototype development fulfil the main expected functionalities as per Milestone M2.4.

LSP	signalling tests		
	LSP signalling tests	s in LSC domain	
No	Test Card	Test name	Status
1	G ² MPLS-TC-1.1	LSC node initialization	Passed
2	G ² MPLS-TC-1.2	Transport Plane notifications from LSC node	Passed
3	G ² MPLS-TC-1.3	Setup of one bidirectional LSC LSP	Passed
4	G ² MPLS-TC-1.4	Tear down of one bidirectional LSC LSP from HEAD node	Passed
5	G ² MPLS-TC-1.5	Tear down of one bidirectional LSC LSP from TAIL node	Passed
6	G ² MPLS-TC-1.6	Unsuccessful bidirectional LSC LSP setup (failure in HEAD node)	Passed
7	G ² MPLS-TC-1.7	Unsuccessful bidirectional LSC LSP setup (failure in intermediate node)	Passed
8	G ² MPLS-TC-1.8	Unsuccessful bidirectional LSC LSP setup (failure in TAIL node)	Passed
9	G ² MPLS-TC-1.9	Setup of one bidirectional LSC LSP with advance reservation	Passed
10	G ² MPLS-TC-1.10	Tear down of one bidirectional LSC LSP with advance reservation from	Passed
		HEAD node	
	I CD cianollina toota	vin ECC domain	
	LSP signalling tests	SIII ESC domain	
No	Test Card	Test name	Status
No 11	Test Card G ² MPLS-TC-2.1	Test name FSC node initialization	Passed
11 12	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2	Test name FSC node initialization Transport Plane notifications from FSC node	
11 12 13	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP	Passed
11 12 13 14	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node	Passed Passed
11 12 13 14 15	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node	Passed Passed Passed Passed Passed
11 12 13 14 15 16	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node)	Passed Passed Passed Passed Passed Passed
11 12 13 14 15 16 17	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6 G ² MPLS-TC-2.7	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node) Unsuccessful bidirectional FSC LSP setup (failure in intermediate node)	Passed Passed Passed Passed Passed Passed Passed Passed
11 12 13 14 15 16 17 18	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6 G ² MPLS-TC-2.7	FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node) Unsuccessful bidirectional FSC LSP setup (failure in intermediate node) Unsuccessful bidirectional FSC LSP setup (failure in TAIL node)	Passed
11 12 13 14 15 16 17 18 19	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6 G ² MPLS-TC-2.7 G ² MPLS-TC-2.7	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node) Unsuccessful bidirectional FSC LSP setup (failure in intermediate node) Unsuccessful bidirectional FSC LSP setup (failure in TAIL node) Setup of one bidirectional FSC LSP with advance reservation	Passed
11 12 13 14 15 16 17 18	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6 G ² MPLS-TC-2.7	FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node) Unsuccessful bidirectional FSC LSP setup (failure in intermediate node) Unsuccessful bidirectional FSC LSP setup (failure in TAIL node) Setup of one bidirectional FSC LSP with advance reservation Tear down of one bidirectional FSC LSP with advance reservation from	Passed
11 12 13 14 15 16 17 18 19 20	Test Card G ² MPLS-TC-2.1 G ² MPLS-TC-2.2 G ² MPLS-TC-2.3 G ² MPLS-TC-2.4 G ² MPLS-TC-2.5 G ² MPLS-TC-2.6 G ² MPLS-TC-2.7 G ² MPLS-TC-2.7	Test name FSC node initialization Transport Plane notifications from FSC node Setup of one bidirectional FSC LSP Tear down of one bidirectional FSC LSP from HEAD node Tear down of one bidirectional FSC LSP from TAIL node Unsuccessful bidirectional FSC LSP setup (failure in HEAD node) Unsuccessful bidirectional FSC LSP setup (failure in intermediate node) Unsuccessful bidirectional FSC LSP setup (failure in TAIL node) Setup of one bidirectional FSC LSP with advance reservation Tear down of one bidirectional FSC LSP with advance reservation from HEAD node	Passed

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Report on Grid-GMPLS Control Plane functional tests

	Single-domain call	signalling tests	
No	Test Card	Test name	Status
21	G ² MPLS-TC-3.1	Setup of one bidirectional single-domain FSC LSP by G2.NCC module	Passed
22	G ² MPLS-TC-3.2	Teardown of the one bidirectional single-domain FSC LSP by G2.NCC module	Passed
23	G ² MPLS-TC-3.3	Setup of one bidirectional single-domain FSC LSP by G2.CCC module	Passed
24	G ² MPLS-TC-3.4	Teardown of the one bidirectional single-domain FSC LSP by G2.CCC module	Passed
25	G ² MPLS-TC-3.5	Setup of one bidirectional single-domain FSC LSP by G.UNI-GW module	Passed
26	G ² MPLS-TC-3.6	Teardown of the one bidirectional single-domain FSC LSP by G.UNI-GW module	Passed
27	G ² MPLS-TC-3.7	Setup of one bidirectional single-domain FSC LSP by Middleware WS- Agreement client	Passed
28	G ² MPLS-TC-3.8	Teardown of the one bidirectional single-domain FSC LSP by Middleware WS-Agreement client	Passed
	Inter-domain call si	gnalling tests	
No	Test Card	Test name	Status
29	Test Card G ² MPLS-TC-4.1	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC	Passed
29 30	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2	Test name	
29 30	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC	Passed
29 30 G ² N	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases	Passed Passed
29 30 G ² N	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name	Passed Passed Status
29 30 G ² N No 31	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization	Passed Passed Status Passed
29 30 G ² N No 31 32	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1 G ² MPLS-TC-5.2	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization Distribution of TE information through the G.I-NNI interfaces	Passed Passed Status Passed Passed
29 30 G ² N No 31	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1 G ² MPLS-TC-5.2 G ² MPLS-TC-5.3	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization Distribution of TE information through the G.I-NNI interfaces Distribution of Grid information through the G.UNI and G.I-NNI interfaces	Passed Passed Status Passed
29 30 G ² M No 31 32 33	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1 G ² MPLS-TC-5.2 G ² MPLS-TC-5.3 Inter-domain routin	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization Distribution of TE information through the G.I-NNI interfaces Distribution of Grid information through the G.UNI and G.I-NNI interfaces g test cases	Passed Passed Status Passed Passed Passed
29 30 G ² M No 31 32 33	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1 G ² MPLS-TC-5.2 G ² MPLS-TC-5.3 Inter-domain routin Test Card	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization Distribution of TE information through the G.I-NNI interfaces Distribution of Grid information through the G.UNI and G.I-NNI interfaces g test cases Test name	Passed Passed Status Passed Passed Passed Passed Status
29 30 G ² M No 31 32 33	Test Card G ² MPLS-TC-4.1 G ² MPLS-TC-4.2 IPLS routing tests Single-domain rout Test Card G ² MPLS-TC-5.1 G ² MPLS-TC-5.2 G ² MPLS-TC-5.3 Inter-domain routin	Test name Setup of one bidirectional inter-domain FSC LSP by G2.CCC Teardown of the one bidirectional single-domain FSC LSP by G2.CCC ting test-cases Test name I-NNI G2.OSPF-TE instance initialization Distribution of TE information through the G.I-NNI interfaces Distribution of Grid information through the G.UNI and G.I-NNI interfaces g test cases	Passed Passed Status Passed Passed Passed

Table 5.1 Overview of the executed test-cards.

5.2 LSP signalling tests

The G²MPLS LSP signalling tests have been executed in two separate sessions:

- LSC LSP signalling tests
- · FSC LSP signalling tests

The LSC LSP signalling tests have been used to verify the proper work and interaction of modules involved in the LSP signalling in LSC domain and LSC equipment configuration (G².RSVP-TE, LRM, TNRC with Adva TNRC SP plugin, SCNGW).

Similarly, The FSC LSP signalling tests have been used to verify the proper work and interaction of modules involved in the LSP signalling in FSC domain and FSC equipment configuration (G².RSVP-TE, LRM, TNRC with Calient TNRC SP plugin, SCNGW).

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



5.2.1 LSP signalling tests in LSC domain

In this section the results of the tests regarding the single-domain LSP signalling are presented. As shown in Figure 5.1, in the test-bed there are $3 \, G^2 MPLS$ controllers with just I-NNI interfaces between them.




Figure 5.1: Logical topology of the single-domain LSC test-bed.

5.2.1.1 LSC node initialization

Test Card #	est Card # G ² MPLS-TC-1.1		NIVIAL DENIC
Test Card Name	LSC node initialization Authors NXW, PSNC		NAVV, FSINC
	Proper configuration of TNRC and LRM modules:		
Objectives • Configuration files reading			
	Resource and states retrieving from TN equipment via Adva FSP 3000RE		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



Related Test Cards	TNRC SP plugin Information passing from TNRC to LRM Information presenting in VTY None
Topology and DUT details	NODE

Test des	Test description			
Step	Description	Outcome		
1.	Run TNRCD process	 ✓ TNRCD is up and working There is TNRCD process on the system processes list The configuration file was read successfully TNRCD VTY is accessible 		
1.1.	TNRC AP data model is loaded	✓ There are proper equipment and boards information available in TNRCD VTY		
1.2.	TNRC SP retrieved information from equipment	 ✓ There are ports and resources available in TNRCD VTY ○ Ports operational statuses are UP ○ The port bandwidth values are equal to configured in TNRCD equipment configuration file ○ Resources operational statuses are UP ○ Bitmaps show no lambda in use. 		
2.	Run LRM process	 ✓ LRMD is up and working There is LRMD process on the system processes list The configuration file was read successfully LRMD VTY is accessible 		
2.1.	LRM data model is loaded	 ✓ There are proper SCN interfaces, Control Channels, adjacencies, data links and TE-links information available in LRMD VTY The information about data-links are the same as in TNRCD The SCN and TE-link information correspond to data-links and LRMD configuration file 		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



Additional comments

- Preconditions
 - Before the test there should be no already existing cross-connections on equipment. If there will
 be some existing cross-connection (for example: created by Management Plane) then operational
 statuses related to the cross-connection resources will be in down state and cannot be used by
 G²MPLS Control Plane.


Test status	
Passed	

5.2.1.2 Transport Plane notifications from LSC node

Test Card #	Card # G ² MPLS-TC-1.2		
Test Card Name	Transport Plane notifications from LSC node		NXW, PSNC
Objectives	Notification of TNRC and LRM modul state change or in case of wavelength System or Network Operator): States change retrieving from		
Related Test Cards	G ² MPLS-TC-1.1		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	TNRCD and LRMD processes are running on all nodes	 ✓ TNRCD VTY and LRMD VTY are accessible ✓ See G²MPLS-TC-1.1 Step 1 and 2 		
2.	Operational state of a port is set down on Equipment	✓ TNRC SP retrieves information about port operation state change		
2.1.	Notification from TNRC SP is issued to TNRC AP	✓ There is the port state down information in TNRCD VTY		
2.2.	Notification from TNRC AP is issued to upper protocols (LRMD)	 ✓ Changes in LRMD VTY ○ The data-link operational state is DOWN ○ related TE-link has operation state DOWN 		
3.	Status of a free wavelength is set to busy on Equipment via NE management interface	✓ TNRC SP retrieve information about active cross- connections on equipment		
3.1.	Notification from TNRC SP is issued to TNRC AP	✓ There is port state down information present in TNRCD VTY		
3.2.	Notification from TNRC AP is issued to upper protocols (LRMD)	 ✓ Changes in LRMD VTY ○ The data-link operational state is DOWN ○ related TE-link has operation state DOWN 		

Additional comments

- Preconditions
 - Free wavelength is set to busy via selected wavelength cross-connection configuring using NE management interface.

Test status

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Passed

5.2.1.3 Setup of one bidirectional LSC LSP

Test Card # G ² MPLS-TC-1.3		Authoro	NIVIAL DONG
Test Card Name	Setup of one bidirectional LSC LSP	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in ca of LSC LSP setup: LSP setup signalling through 3 LSC nodes via RSVP-TE TN equipments cross-connect configuration Data model information updating		
Related Test Cards	G ² MPLS-TC-1.1		
Topology and DUT details	HEAD G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC

Test desc	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes Create LSP from HEAD	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 		
2.	node	✓ LSP is created and signalled up		
2.1.	HEAD node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to intermediate node 		
2.2.	HEAD node: TNRC AP	√ There is cross-connection information in TNRCD VTY		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



	notification is issued to upper protocols on cross-connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is less available port bandwidth (port, datalink, TE-link)
2.3.	Intermediate node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to TAIL node
2.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection setup	 ✓ There is cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is less available port bandwidth (port, datalink, TE-link)
2.5.	TAIL node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized back to HEAD node via intermediate node
2.6.	TAIL node: TNRC AP notification is issued to upper protocols on cross-connection setup	 ✓ There is cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is less available port bandwidth (port, datalink, TE-link)

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - After the test the created LSP is up and running. There are related cross-connections on TN equipment.


Test status		
Passed		

5.2.1.4 Tear down of one bidirectional LSC LSP from HEAD node

Test Card #	G ² MPLS-TC-1.4		
Test Card Name	Tear down of one bidirectional LSC LSP from HEAD node	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of LSC LSP teardown: • LSP teardown signalling through 3 LSC nodes via RSVP-TE from the ingress node • TN equipments cross-connect deletion • Data model information updating		
Related	$G^2MPLS-TC-1.1$, $G^2MPLS-TC-1.3$		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test de	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 		
2.	Create LSP from HEAD node	 ✓ LSP is created and signalled up ✓ See G²MPLS-TC-1.3 Step 2 		
3.	Destroy LSP from HEAD node	✓ LSP is signalled down from HEAD node and destroyed		
3.1.	HEAD node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to intermediate node 		
3.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link) 		
3.3.	Intermediate node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to TAIL node 		
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link) 		
3.5.	TAIL node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized back to HEAD node via intermediate node 		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	TAIL node: TNRC AP	✓ There is no cross-connection information in TNRC VTY
3.6.	notification is issued to	✓ Changes in LRMD VTY and in TNRCD VTY
3.0.	upper protocols on cross-	 Max available port bandwidth is back (port, data-
	connection deletion	link, TE-link)

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.


Test status		
Passed		

5.2.1.5 Tear down of one bidirectional LSC LSP from TAIL node

Test Card # G ² MPLS-TC-1.5			
Test Card Name	Tear down of one bidirectional LSC LSP from TAIL node	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of LSC LSP teardown: • LSP teardown signalling through 3 LSC nodes via RSVP-TE from the egress node • TN equipments cross-connect deletion • Data model information updating		
Related Test Cards	G ² MPLS-TC-1.1, G ² MPLS-TC-1.3		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 			
2.	Create LSP from HEAD node	 ✓ LSP is created and signalled up ✓ See G²MPLS-TC-1.3 Step 2 			
3.	Destroy LSP from TAIL node	✓ LSP is signalled down from HEAD node and destroyed			
3.1.	TAIL node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to intermediate node 			
3.2.	TAIL node: TNRC AP notification is issued to upper protocols on cross-connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link) 			
3.3.	Intermediate node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to HEAD node 			
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link) 			
3.5.	HEAD node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized back to TAIL node via intermediate node 			
3.6.	HEAD node: TNRC AP	✓ There is no cross-connection information in TNRC VTY			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



notification is issued to	✓ Changes in LRMD VTY and in TNRCD VTY
upper protocols on cross-	 Max available port bandwidth is back (port, data-
connection deletion	link, TE-link)

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

est status	
assed	

5.2.1.6 Unsuccessful bidirectional LSC LSP setup (failure in HEAD node)

Took Cond #	O ² MDI O TO 4 C		
Test Card #	G ² MPLS-TC-1.6		
Test Card Name	Unsuccessful bidirectional LSC LSP setup (failure in HEAD node)	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of LSC LSP setup failure in HEAD node		
Related Test Cards	G ² MPLS-TC-1.1, G ² MPLS-TC-1.3		
Topology and DUT details	HEAD G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	TAIL G2 RSVP-TE LRM TNRC

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 			
2.	Create LSP from HEAD node	 ✓ LSP creation is unsuccessful ✓ See G²MPLS-TC-1.3 Step 2.1, 2.2 			
2.1.	Outgoing TE-link is not present in HEAD node	✓ LSP is in "Down" state and no Path signalling and cross- connection is issued			
2.2.	Outgoing TE-link is down in HEAD node	✓ LSP is in "Down" state and no Path signalling and cross- connection is issued			
2.3.	Outgoing data-link is not present in HEAD node	 ✓ Selection of data-link in TE-link fails ✓ LSP is in "Down" state and no Path signalling and cross-connection is issued 			
2.4.	Outgoing data-link is down in LRMD in HEAD node	 ✓ Selection of data-link in TE-link fails ✓ LSP is in "Down" state and no Path signalling and cross-connection is issued 			
2.5.	Outgoing label is not present in HEAD node	✓ LSP is in "Down" state and no Path signalling and cross- connection is issued			
2.6.	Outgoing label is not free in TNRCD in HEAD node	 ✓ Selection of label in data-link fails ✓ LSP is in "Down" state and no Path signalling and cross-connection is issued 			
2.7.	Cross-connection fails in TNRCD in HEAD node	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to intermediate node ✓ Notification of unsuccessful cross-connection setup is issued to upper protocols ○ PathTear is issued to intermediate node and LSP is in "Down" state 			

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - After the test the situation is the same as before the test.

Failure conditions related to a lack of resource presence (label, data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of label can happen when there is existing cross-connection using the label.

Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment mis-configuration or lack of light.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

Test status	
Passed	

5.2.1.7 Unsuccessful bidirectional LSC LSP setup (failure in intermediate node)

Test Card #	G ² MPLS-TC-1.7		
Test Card Name	Unsuccessful bidirectional LSC LSP setup (failure in intermediate node)	Authors	NXW, PSNC
Objectives	Verification of proper work of modules of LSC LSP setup failure in intermedi		, SCNGW and G2.RSVP-TE in case
Related Test Cards	G ² MPLS-TC-1.1, G ² MPLS-TC-1.3		
Topology and DUT details	HEAD G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	TAIL G2 RSVP-TE LRM TNRC

Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 			
2.	Create LSP from HEAD node	 ✓ LSP creation is unsuccessful ✓ See G²MPLS-TC-1.3 Step 2.1, 2.2, 2.3, 2.4 			
2.1.	Outgoing TE-link is not present in intermediate node	 ✓ Intermediate node: ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD node: 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	,		
			LSP is in "Down" Cross connection is destroyed.
			Cross-connection is destroyed
		✓	Intermediate node:
			 ERO process fails
			 PathErr is sent upstream
	Outgoing TE-link is down in		 LSP is in "Down" and no Path is issued
2.2.	intermediate node		downstream
	intermediate node	./	HEAD node:
		•	
			LSP is in "Down"
			 Cross-connection is destroyed
		✓	Intermediate node:
			 data-link selection from TE-link fails
			 ERO process fails
	Outgoing data-link is not		 PathErr is sent upstream
2.3.	present in intermediate		 LSP is in "Down" and no Path is issued
2.5.	•		
	node	,	downstream
		✓	HEAD node:
			LSP is in "Down"
			 Cross-connection is destroyed
		✓	Intermediate node:
			 data-link selection from TE-link fails
			ERO process fails
	Outgoing data link is down		
0.4	Outgoing data-link is down		PathErr is sent upstream
2.4.	in LRMD in intermediate		 LSP is in "Down" and no Path is issued
	node		downstream
		✓	HEAD node:
			LSP is in "Down"
			 Cross-connection is destroyed
		✓	Intermediate node:
			o data-link selection from TE-link fails
	Outroing Johalia not		ERO process fails Path Fire is contained as a second contain
	Outgoing label is not		 PathErr is sent upstream
2.5.	present in intermediate		 LSP is in "Down" and no Path is issued
	node		downstream
		✓	HEAD node:
			LSP is in "Down"
			 Cross-connection is destroyed
		√	Intermediate node:
			data link a dastina faces TE link falls
			 ERO process fails
	Outgoing label is not free in		 PathErr is sent upstream
2.6.	TNRCD in intermediate		 LSP is in "Down" and no Path is issued
	node		downstream
		✓	HEAD node:
			LSP is in "Down"
			Cross-connection is destroyed
		√	Intermediate node:
		•	
			 notification of unsuccessful cross-connection setup
	Cross-connection fails in		is issued to upper protocols
2.7.	TNRCD in intermediate		 ERO process fails
	node		 PathErr is sent upstream
			PathTear is send downstream
			 LSP is in "Down" and no Path is issued
		l	U LUI IS III DUWII AHU HU FAUH IS ISSUEU

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



downstream
✓ HEAD node:
○ LSP is in "Down"
 Cross-connection is destroyed

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Failure conditions related to a lack of resource presence (label, data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of label can happen when there is existing cross-connection using the label.

Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment misconfiguration or lack of light.


Test status	
Passed	

5.2.1.8 Unsuccessful bidirectional LSC LSP setup (failure in TAIL node)

Test Card #	G ² MPLS-TC-1.8		
Test Card Name	Unsuccessful bidirectional LSC LSP setup (failure in TAIL node)	Authors	NXW, PSNC
Objectives	Objectives Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of LSC LSP setup failure in TAIL node		
Related G ² MPLS-TC-1.1, G ² MPLS-TC-1.3			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test de	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 			
2.	Create LSP from HEAD node	 ✓ LSP creation is unsuccessful ✓ See G²MPLS-TC-1.3 Step 2.1, 2.2, 2.3, 2.4, 2.5, 2.6 			
2.1.	Outgoing TE-link is not present in TAIL node	 ✓ TAIL node: TNA resolving process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed 			
2.2.	Outgoing TE-link is down in TAIL node	 ✓ TAIL node: ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed 			
2.3.	Outgoing data-link is not present in TAIL node	 ✓ TAIL node: data-link selection from TE-link fails ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



		Cross-connection is destroyed
		✓ TAIL node:
2.4.	Outgoing data-link is down in LRMD in TAIL node	 o data-link selection from TE-link fails o ERO process fails o PathErr is sent upstream o LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: o LSP is in "Down" o Cross-connection is destroyed
2.5.	Outgoing label is not present in TAIL node	 ✓ TAIL node: data-link selection from TE-link fails ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed
2.6.	Outgoing label is not free in TNRCD in TAIL node	 ✓ TAIL node: data-link selection from TE-link fails ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed
2.7.	Cross-connection fails in TNRCD in TAIL node	 ✓ TAIL node: notification of unsuccessful cross-connection setup is issued to upper protocols ERO process fails PathErr is sent upstream PathTear is send downstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Failure conditions related to a lack of resource presence (label, data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of label can happen when there is existing cross-connection using the label.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment mis-configuration or lack of light.

Test status		
Passed		

5.2.1.9 Setup of one bidirectional LSC LSP with advance reservation

Test Card #	G ² MPLS-TC-1.9			
Test Card Name	Setup of one bidirectional LSC LSP with advance reservation	LSC LSP Authors NXW, PSNC		
Objectives	verification of proper work of modules TNRC, LRM, SCNGWS and G2.RSVPTE in case of LSC LSP advance reservation: • LSP setup with advance reservation signalling through 3 LSC nodes via RSVP-TE • LSP activation after reservation start time • LSP teardown after reservation end time • TN equipment reconfiguration • Data model information updating			
Related Test Cards	G ² MPLS-TC-1.1, G ² MPLS-TC-1.4			
Topology and DUT details	G2 RSVP-TE	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Test de	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 		
2.	Create LSP with advance reservation from HEAD node	✓ Advance LSP is created and activated		
2.1.	HEAD node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ LSP setup with advance reservation is signalized to intermediate node 		
2.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
2.3.	Intermediate node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ○ LSP setup with advance reservation is signalized to intermediate node 		
2.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
2.5.	TAIL node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ○ LSP setup with advance reservation is signalized to intermediate node 		
2.6.	TAIL node: TNRC AP notification is issued to upper protocols on crossconnection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
3.	LSP is activated	✓ LSP up and running		
3.1.	HEAD node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification 		
3.2.	Intermediate node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification 		
3.3.	HEAD node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification 		
3.4.	LSP is teardown	 ✓ LSP is destroyed ✓ See G²MPLS-TC-1.4 Step 3 		
3.5.	HEAD node: TNRC AP issues cross-connection deletion	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification ✓ G2.RSVP-TED initiate LSP TearDown ✓ LSP goes "down" and is destroyed 		
3.6.	Intermediate node: TNRC AP issues cross-connection	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification 		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



	deletion	
3.7.	TAIL node: TNRC AP issues cross-connection deletion	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.


Decead	
Passed	

5.2.1.10 Tear down of one bidirectional LSC LSP with advance reservation from HEAD node

Test Card #	G ² MPLS-TC-1.10		
Test Card Name Tear down of one bidirectional LSC LSP with advance reservation from HEAD node		Authors	NXW, PSNC
Objectives	verification of proper work of modules TNRC, LRM, SCNGWS and G2.RSVPTE i of LSC LSP advance reservation teardown: • LSP setup with advance reservation signalling through 3 LSC nodes via F		ling through 3 LSC nodes via RSVP-
Related Test Cards	G ² MPLS-TC-1.1, G ² MPLS-TC-1.9		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test de	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-1.1 Step 1 and 2 		
2.	Create LSP with advance reservation from HEAD node	 ✓ Advance LSP is created and activated ✓ See G2MPLS-TC-1.9 Step 2 and 3 		
3.	Destroy LSP before reservation START_TIME	✓ LSP is signalled down from HEAD node and destroyed		
3.1.	HEAD node: cross- connection unreservation request is send from G2.RSVP-TED to TNRC	 ✓ LSP is "down" in G2.RSVP-TED ✓ LSP teardown is signalized to intermediate node 		
3.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link) 		
3.3.	Intermediate node: cross- connection unreservation request is send from G2.RSVP-TED to TNRCD	✓ LSP is "down" in G2.RSVP-TED		
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross-connection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link) 		
3.5.	TAIL node: cross- connection unreservation request is send from G2.RSVP-TED to TNRCD	✓ LSP is "down" in G2.RSVP-TED o LSP teardown is signalized back to HEAD node via intermediate node		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.6.	TAIL node: TNRC AP notification is issued to upper protocols on crossconnection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link)
------	-------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - After the test the situation is the same as before the test.

Test status	
Passed	

5.2.2 LSP signalling tests in FSC domain

In this section are presented the results of the tests regarding the single-domain LSP signalling with FSC switching capability. As shown in Figure 5.2, in the test-bed there are 4 I-NNI G²MPLS controllers.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115







Figure 5.2: Logical topology of the single-domain FSC test-bed.

5.2.2.1 FSC node initialization

Test Card #	est Card # G ² MPLS-TC-2.1		NVW DONG
Test Card Name	FSC node initialization	Authors NXW, PSNC	
Objectives	Proper configuration of TNRC and LR	g from TN eq n RC to LRM	uipment via Calient DiamondWave
Related Test Cards	None		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test desc	Test description			
Step	Description	Outcome		
1.	Run TNRCD process	 ✓ TNRCD is up and working There is TNRCD process on the system processes list The configuration file was read successfully TNRCD VTY is accessible 		
1.1.	TNRC AP data model is loaded	✓ There are proper equipment and boards information available in TNRCD VTY		
1.2.	TNRC SP retrieved information from equipment	 ✓ There are ports and resources available in TNRCD VTY ○ Ports operational statuses are UP ○ The port bandwidth values are equal to configured in TNRCD equipment configuration file 		
2.	Run LRMD process	 ✓ LRMD is up and working There is TNRCD process on the system processes list The configuration file was read successfully LRMD VTY is accessible 		
2.1.	LRMD data model is loaded	 ✓ There are proper SCN interfaces, Control Channels, adjacencies, data links and TE-links information available in LRMD VTY The information about data-links are the same as in TNRCD The SCN and TE-link information correspond to data-links and LRMD configuration file The bundling operation on TE-Links containing more than one data-link is correct 		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Additional comments

- Preconditions
 - Before the test there should be no already existing cross-connections on equipment. If there will be some existing cross-connection (for example: created by Management Plane) then operational statuses related to the cross-connection resources will be in down state and cannot be used by G²MPLS Control Plane.

Test status	
Passed	

5.2.2.2 Transport Plane notifications from FSC node

Test Card #	G ² MPLS-TC-2.2		
Test Card Name	Transport Plane notifications from FSC node	Authors	NXW, PSNC
Objectives	Notification of TNRC and LRM modules in FSC node in case of resource operational state change or in case of wavelength external usage (by Network Management System or Network Operator): • States change retrieving from TN equipment via Calient DiamondWave FiberConnect TNRC SP plugin • Information passing from TNRC to LRM • Data Model information updating		
Related Test Cards	G ² MPLS-TC-2.1		
Topology and DUT details	NODE		

Test description

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Step	Description	Outcome	
1.	TNRCD and LRMD processes are running on all nodes	 ✓ TNRCD VTY and LRMD VTY are accessible ✓ See G²MPLS-TC-2.1 Step 1 and 2 	
2.	Operational state of a port is set down on Equipment	✓ TNRC SP retrieve information about port operation state change	
2.1.	Notification from TNRC SP is issued to TNRC AP	✓ There is the port state down information present in TNRCD VTY	
2.2.	Notification from TNRC AP is issued to upper protocols (LRMD)	 ✓ Changes in LRMD VTY ○ The data-link operational state is DOWN ○ related TE-link has operation state DOWN 	

Additional comments	
None.	

Test status	
Passed	


5.2.2.3 Setup of one bidirectional FSC LSP

Test Card #	G ² MPLS-TC-2.3	Authors	NXW, PSNC		
Test Card Name	Setup of one bidirectional FSC LSP	Authors	NAVV, PSINC		
	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of FSC LSP setup:				
Objectives	 LSP setup signalling through 3 FSC nodes via RSVP-TE 				
	TN equipments cross-connect configuration				
	Data model information updating				
Related Test Cards	G ² MPLS-TC-2.1				

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4





Test de	scription	
Step	Description	Outcome
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2
2.	Create LSP from HEAD node	✓ LSP is created and signalled up
2.1.	HEAD node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to intermediate node
2.2.	HEAD node: TNRC AP notification is issued to upper protocols on crossconnection setup	 ✓ There is cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no available port bandwidth (port, datalink, TE-link)
2.3.	Intermediate node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to TAIL node
2.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection setup	 ✓ There is cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no available port bandwidth (port, datalink, TE-link)
2.5.	TAIL node: cross- connection setup request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized back to HEAD node via intermediate node
2.6.	TAIL node: TNRC AP notification is issued to upper protocols on crossconnection setup	 ✓ There is cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no available port bandwidth (port, datalink, TE-link)

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - After the test the created LSP is up and running. There are related cross-connections on TN equipment.

Test status		
Passed		

5.2.2.4 Tear down of one bidirectional FSC LSP from HEAD node

Test Card #	G ² MPLS-TC-2.4			
Test Card Name	Tear down of one bidirectional FSC LSP from HEAD node	Authors	NXW, PSNC	
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of FSC LSP teardown: • LSP teardown signalling through 3 FSC nodes via RSVP-TE from the ingress node • TN equipments cross-connect deletion • Data model information updating			
Related Test Cards	G ² MPLS-TC-2.1, G ² MPLS-TC-2.3			
Topology and DUT details	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Test de	scription	
Step	Description	Outcome
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2
2.	Create LSP from HEAD node	 ✓ LSP is created and signalled up ✓ See G²MPLS-TC-2.3 Step 2
3.	Destroy LSP from HEAD node	✓ LSP is signalled down from HEAD node and destroyed
3.1.	HEAD node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to intermediate node
3.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection deletion	 ✓ There is no cross-connection information in TNRC VTY ✓ Changes in LRMD VTY and in TNRC VTY ○ Max available port bandwidth is back (port, datalink, TE-link)
3.3.	Intermediate node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to TAIL node
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link)
3.5.	TAIL node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized back to HEAD node via intermediate node
3.6.	TAIL node: TNRC AP notification is issued to upper protocols on cross-connection deletion	 ✓ There is no cross-connection information in TNRC VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link)

Additional comments

- Preconditions
 - $\circ\quad$ Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Test status			
Passed			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



5.2.2.5 Tear down of one bidirectional FSC LSP from TAIL node

Test Card #				
Test Card Name	Tear down of one bidirectional FSC LSP from TAIL node	Authors	NXW, PSNC	
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of FSC LSP teardown: • LSP teardown signalling through 3 FSC nodes via RSVP-TE from the egress node • TN equipments cross-connect deletion • Data model information updating			
Related Test Cards	G ² MPLS-TC-2.2, G ² MPLS-TC-2.3			
Topology and DUT details	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	

Test de	scription	
Step	Description	Outcome
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2
2.	Create LSP from HEAD node	 ✓ LSP is created and signalled up ✓ See G²MPLS-TC-2.3 Step 2
3.	Destroy LSP from TAIL node	✓ LSP is signalled down from HEAD node and destroyed
3.1.	TAIL node: cross- connection deletion request is send from G2.RSVP-TED to TNRC	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to intermediate node
3.2.	TAIL node: TNRC AP notification is issued to upper protocols on crossconnection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link)

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.3.	Intermediate node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized to HEAD node
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection deletion	 ✓ There is no cross-connection information in TNRC VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link)
3.5.	HEAD node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ Cross-connection deletion on equipment ✓ LSP teardown is signalized back to TAIL node via intermediate node
3.6.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection deletion	 ✓ There is no cross-connection information in TNRCD VTY ✓ Changes in LRMD VTY and in TNRCD VTY ○ Max available port bandwidth is back (port, datalink, TE-link)

Additional comments


- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

5.2.2.6 Unsuccessful bidirectional FSC LSP setup (failure in HEAD node)

Test Card # G ² MPLS-TC-2.6			
Test Card Name	Unsuccessful bidirectional FSC LSP setup (failure in HEAD node)	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of FSC LSP setup failure in HEAD node		
Related Test Cards	G ² MPLS-TC-2.1, G ² MPLS-TC-2.3		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVPTED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2 		
2.	Create LSP from HEAD node	 ✓ LSP creation is unsuccessful ✓ See G²MPLS-TC-2.3 Step 2.1, 2.2 		
2.1.	Outgoing TE-link is not present in HEAD node	✓ LSP is in "Down" state and no Path signalling and cross- connection is issued		
2.2.	Outgoing TE-link is down in HEAD node	✓ LSP is in "Down" state and no Path signalling and cross- connection is issued		
2.3.	Outgoing data-link is not present in HEAD node	 ✓ Selection of data-link in TE-link fails ✓ LSP is in "Down" state and no Path signalling and cross-connection is issued 		
2.4.	Outgoing data-link is down in LRMD in HEAD node	 ✓ Selection of data-link in TE-link fails ✓ LSP is in "Down" state and no Path signalling and cross-connection is issued 		
2.5.	Cross-connection fails in TNRCD in HEAD node	 ✓ LSP is "installed" in G2.RSVP-TED ✓ Cross-connection setup on equipment ✓ LSP setup is signalized to intermediate node ✓ Notification of unsuccessful cross-connection setup is issued to upper protocols ○ PathTear is issued to intermediate node and LSP is in "Down" state 		

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Failure conditions related to a lack of resource presence (data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down or there is already existing cross-connection.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment mis-configuration or lack of light.

Test status	
Passed	

5.2.2.7 Unsuccessful bidirectional FSC LSP setup (failure in intermediate node)

To at Oamel #	O ² MDI O TO O 7		
Test Card #	G ² MPLS-TC-2.7		
Test Card Name	Unsuccessful bidirectional FSC LSP setup (failure in intermediate node)		NXW, PSNC
Objectives	Verification of proper work of modules of FSC LSP setup failure in intermed		I, SCNGW and G2.RSVP-TE in case
Related Test Cards	G ² MPLS-TC-2.1, G ² MPLS-TC-2.3		
	HEAD	INTMD	TAIL
Topology and DUT details	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC

Test description			
Step	Description	Outcome	
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVPTED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2 	
2.	Create LSP from HEAD	✓ LSP creation is unsuccessful	

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	node	✓ See G ² MPLS-TC-2.3 Step 2.1, 2.2, 2.3, 2.4
2.1.	Outgoing TE-link is not present in intermediate node	 ✓ intermediate node: ○ ERO process fails ○ PathErr is sent upstream ○ LSP is in "Down" and no Path is issued downstream ✓ HEAD node: ○ LSP is in "Down" ○ Cross-connection is destroyed
2.2.	Outgoing TE-link is down in intermediate node	 ✓ intermediate node: ○ ERO process fails ○ PathErr is sent upstream ○ LSP is in "Down" and no Path is issued downstream ✓ HEAD node: ○ LSP is in "Down" ○ Cross-connection is destroyed
2.3.	Outgoing data-link is not present in intermediate node	 ✓ intermediate node: o data-link selection from TE-link fails o ERO process fails o PathErr is sent upstream o LSP is in "Down" and no Path is issued downstream ✓ HEAD node: o LSP is in "Down" o Cross-connection is destroyed
2.4.	Outgoing data-link is down in LRMD in intermediate node	 ✓ intermediate node: ○ data-link selection from TE-link fails ○ ERO process fails ○ PathErr is sent upstream ○ LSP is in "Down" and no Path is issued downstream ✓ HEAD node: ○ LSP is in "Down" ○ Cross-connection is destroyed
2.5.	Cross-connection fails in TNRCD in intermediate node	 ✓ intermediate node: o notification of unsuccessful cross-connection setup is issued to upper protocols o ERO process fails o PathErr is sent upstream o PathTear is send downstream o LSP is in "Down" and no Path is issued downstream ✓ HEAD node: o LSP is in "Down" o Cross-connection is destroyed

Additional comments

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Failure conditions related to a lack of resource presence (data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down or there is already existing cross-connection.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment mis-configuration or lack of light.

Test status	
Passed	

5.2.2.8 Unsuccessful bidirectional FSC LSP setup (failure in TAIL node)

Test Card #	G ² MPLS-TC-2.8		
Test Card Name	Unsuccessful bidirectional FSC LSP setup (failure in TAIL node)	Authors	NXW, PSNC
Objectives	Verification of proper work of modules TNRC, LRM, SCNGW and G2.RSVP-TE in case of FSC LSP setup failure in TAIL node		
Related Test Cards	G ² MPLS-TC-2.1, G ² MPLS-TC-2.3		
Topology and DUT details	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC	G2 RSVP-TE LRM TNRC

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVPTED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2 			
2.	Create LSP from HEAD node	 ✓ LSP creation is unsuccessful ✓ See G²MPLS-TC-2.3 Step 2.1, 2.2, 2.3, 2.4, 2.5, 2.6 			
2.1.	Outgoing TE-link is not present in TAIL node	 ✓ TAIL node: TNA resolving process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed 			
2.2.	Outgoing TE-link is down in TAIL node	 ✓ TAIL node: ○ ERO process fails ○ PathErr is sent upstream ○ LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: ○ LSP is in "Down" ○ Cross-connection is destroyed 			
2.3.	Outgoing data-link is not present in TAIL node	 ✓ TAIL node: data-link selection from TE-link fails ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed 			
2.4.	Outgoing data-link is down in LRMD in TAIL node	 ✓ TAIL node: data-link selection from TE-link fails ERO process fails PathErr is sent upstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" Cross-connection is destroyed 			
2.5.	Cross-connection fails in TNRCD in TAIL node	 ✓ TAIL node: notification of unsuccessful cross-connection setup is issued to upper protocols ERO process fails PathErr is sent upstream PathTear is send downstream LSP is in "Down" and no Path is issued downstream ✓ HEAD and intermediate node: LSP is in "Down" 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



Cross-connection is destroyed

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.

Failure conditions related to a lack of resource presence (data-link, TE-link) can be achieved by incorrect LSP request configuration in G2.RSVP-TE.

Failure conditions related to down state of data-link and TE-link can happen when TN equipment port is set to down or there is already existing cross-connection.

Cross-connection fails in TNRC during setup when alarms appear on TN equipment because of TN equipment misconfiguration or lack of light.


Test status	
Passed	

5.2.2.9 Setup of one bidirectional FSC LSP with advance reservation

Test Card #	G ² MPLS-TC-2.9		
Test Card Name	Setup of one bidirectional FSC LSP with advance reservation	Authors	NXW, PSNC
Objectives	verification of proper work of modules case of FSC LSP advance reservatio LSP setup with advance reservation LSP activation after reservation LSP teardown after reservation TN equipment reconfiguration Data model information update	n: rvation signal on start time on end time	, SCNGWS and G2.RSVP-TE in ling through 3 FSC nodes via RSVP-
Related Test Cards	G ² MPLS-TC-2.1, G ² MPLS-TC-2.4		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVPTED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2 		
2.	Create LSP with advance reservation from HEAD node	✓ Advance LSP is created and activated		
2.1.	HEAD node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ✓ LSP setup with advance reservation is signalized to intermediate node 		
2.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
2.3.	Intermediate node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ○ LSP setup with advance reservation is signalized to intermediate node 		
2.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross- connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
2.5.	TAIL node: cross- connection reservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "installed" in G2.RSVP-TED ○ LSP setup with advance reservation is signalized to intermediate node 		
2.6.	TAIL node: TNRC AP notification is issued to upper protocols on cross-connection setup	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is new advance reservation (resource, port, data-link, TE-link) 		
3.	LSP is activated	✓ LSP up and running		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.1.	HEAD node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification
3.2.	Intermediate node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification
3.3.	HEAD node: TNRC AP issues cross-connection setup	 ✓ Cross-connection configured on equipment ✓ Upper protocols notification
3.4.	LSP is teardown	 ✓ LSP is destroyed ✓ See G²MPLS-TC-2.4 Step 3
3.5.	HEAD node: TNRC AP issues cross-connection deletion	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification ✓ G2.RSVP-TED initiate LSP TearDown ✓ LSP goes "down" and is destroyed
3.6.	Intermediate node: TNRC AP issues cross-connection deletion	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification
3.7.	TAIL node: TNRC AP issues cross-connection deletion	 ✓ Cross-connection destroyed on equipment ✓ Upper protocols notification

Additional comments

- Preconditions
 - o Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - o After the test the situation is the same as before the test.


Test status	
Passed	

5.2.2.10 Tear down of one bidirectional FSC LSP with advance reservation from HEAD node

Test Card #	Test Card # G ² MPLS-TC-2.10			
Test Card Name Test Card Name Test Card Name LSP with advance reservation from HEAD node		Authors	NXW, PSNC	
	verification of proper work of modules TNRC, LRM, SCNGWS and G2.RSVP-TE in case of FSC LSP advance reservation teardown:			
Objectives	 LSP setup with advance reservation signalling through 3 FSC nodes via RSVP-TE LSP teardown before reservation activation time 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVPTED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent ✓ See G²MPLS-TC-2.1 Step 1 and 2 			
2.	Create LSP with advance reservation from HEAD node	 ✓ Advance LSP is created and activated ✓ See G2MPLS-TC-2.9 Step 2 and 3 			
3.	Destroy LSP before reservation START_TIME	✓ LSP is signalled down from HEAD node and destroyed			
3.1.	HEAD node: cross- connection unreservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ✓ LSP teardown is signalized to intermediate node 			
3.2.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link) 			
3.3.	Intermediate node: cross- connection unreservation request is send from G2.RSVP-TED to TNRCD	✓ LSP is "down" in G2.RSVP-TED			
3.4.	Intermediate node: TNRC AP notification is issued to upper protocols on cross-connection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link) 			
3.5.	TAIL node: cross- connection unreservation request is send from G2.RSVP-TED to TNRCD	 ✓ LSP is "down" in G2.RSVP-TED ○ LSP teardown is signalized back to HEAD node via intermediate node 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.6.	TAIL node: TNRC AP notification is issued to upper protocols on cross-connection unreserve	 ✓ Changes in LRMD VTY and in TNRCD VTY ○ There is no advance reservation (resource, port, data-link, TE-link)
------	--------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------

Additional comments

- Preconditions
 - Before the test all needed resources by the LSP should be available and free.
- Postconditions
 - After the test the situation is the same as before the test.

Test status			
Passed			

5.3 **G**²MPLS call signalling tests

The G²MPLS call signalling tests have been executed in two separate sessions:

- single-domain call signalling tests
- Inter-domain call signalling tests

The single-domain tests have been used to verify the proper work and interaction of that modules involved in just one G²MPLS domain signalling (mainly G2.NCC, RC and G².RSVP-TE).

The inter-domain tests, instead, have been used to verify the proper work and interaction of those modules involved in the multi-domain signalling (mainly G2.NCC and G.ENNI-RSVP).

In the next two sessions the results of the two sessions of tests are shown.

5.3.1 Single-domain call signalling tests

In this section the results of the tests regarding the single-domain call signalling are presented. As shown in Figure 5.3Błąd! Nie można odnaleźć źródła odwołania., in the test-bed there are 6 different G²MPLS controllers: 4 of them (Node 1, 2, 3 and 4) have been used as INNI nodes, and the other 2 as G.UNI-GW clients.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Figure 5.3: Logical topology of the single-domain FSC test-bed for G2MPLS Call signalling tests.

5.3.1.1 Setup of one bidirectional single-domain FSC LSP by G2.NCC module

Test Card #	Test Card # G ² MPLS-TC-3.1		
Test Card Name	Setup of one bidirectional single- domain FSC LSP by G2.NCC module	Authors	NXW, PSNC, UESSEX
Objectives	Verification of proper work of modules G2.NCC, RC, TNRC, LRM, SCNGW and G2.RSVP-TE in case of SPC Call and FSC LSP setup: Call setup signalling through 2 G2.NCC instances (HEAD and TAIL node) LSP setup signalling through 2 FSC nodes via RSVP-TE TN equipments cross-connect configuration Data model information updating		
Related Test Cards	G ² MPLS-TC-1.3		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





.

Test de	Test description				
Step	Description	Outcome			
1.	G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 			
2.	Create Call from HEAD node G2.NCC	✓ Call is created and signalled up			
2.1.	HEAD node: Setup request is sent from G2.NCC to TAIL node	 ✓ Setup Indication is received from TAIL node G2.NCC ✓ Setup Confirm is sent from G2.NCC to TAIL node ✓ Call is "active" in G2.NCC ✓ Recovery bundle is created by RC 			
2.2.	TAIL node: Setup request is received from HEAD node G2.NCC	 ✓ Setup Indication is sent from G2.NCC to HEAD node ✓ Setup Confirm is received from TAIL node G2.NCC ✓ Call is "active" in G2.NCC ✓ Recovery bundle is created in RC 			
3.	Create LSP from HEAD node RC	✓ LSP is created and signalled up by RC			
3.1.	HEAD node: LSP and cross-connection setup	✓ See G ² MPLS-TC-1.3: steps 2.1. and 2.2.			
3.2.	TAIL node: LSP and cross- connection setup	✓ See G ² MPLS-TC-1.3 steps 2.5. and 2.6.			

Additional comments

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.NCC

Test status		
Passed		

5.3.1.2 Teardown of the one bidirectional single-domain FSC LSP by G2.NCC module

Test Card #	G ² MPLS-TC-3.2				
Test Card Name	Teardown of the one bidirectional single-domain FSC LSP by G2.NCC module	Authors	NXW, PSNC, UESSEX		
Objectives	Verification of proper work of modules G2.NCC, RC, TNRC, LRM, SCNGW and G2.RSVP-TE in case of SPC Call and FSC LSP teardown: • Call teardown signalling through 2 FSC nodes G2.NCC instances (HEAD and TAIL node) • LSP teardown signalling through 2 FSC nodes via G2.RSVP-TE • TN equipments cross-connect deletion • Data model information updating				
Related Test Cards	G ² MPLS-TC-1.4, G ² MPLS-TC-3.1	G ² MPLS-TC-1.4, G ² MPLS-TC-3.1			
Topology and DUT details	G2.NCC RC G2 RSVP-TE		G2.NCC RC RC G2RSVP-TE		

Test description		
Step	Description	Outcome

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



1.	G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on all nodes		TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible TE-link/CC/SCN-if bindings are consistent
2.	Create Call from HEAD node G2.NCC	✓	See G ² MPLS-TC-3.1: step 2.
3.	Create LSP from HEAD node RC	✓	See G ² MPLS-TC-3.1: step 3.
4.	Destroy Call from HEAD node G2.NCC	✓	Call is signalled down from HEAD node G2.NCC and destroyed
4.1.	HEAD node: Release Request is sent from G2.NCC to TAIL node	✓ ✓ ✓	Release Indication is received from TAIL node G2.NCC Call is "idle" in G2.NCC and is destroyed Recovery bundle is destroyed in RC
4.2.	TAIL node: Release Request is received from HEAD node G2.NCC	* * *	Troidado indication io done nom de indication io de inexastration
5.	Destroy LSP from HEAD node RC	✓	LSP is signalled down from HEAD node RC and destroyed
5.1.	HEAD node: TNRC AP notification is issued to upper protocols on cross-connection deletion	√	See G ² MPLS-TC-1.4: steps 3.1. and 3.2.
5.2.	TAIL node: cross- connection deletion request is send from G2.RSVP-TED to TNRCD	√	See G ² MPLS-TC-1.4: steps 3.5. and 3.6.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to G2.NCC should be removed
- Post-conditions:
 - o new persistency files are created for G2.NCC

Test status			
Passed			

5.3.1.3 Setup of one bidirectional single-domain FSC LSP by G2.CCC module

	Test Card #	G ² MPLS-TC-3.3	Authors	NXW, PSNC, UESSEX
--	-------------	----------------------------	---------	-------------------

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	Control Plane functional				
Test Card Name	Setup of one bidired domain FSC LSP be module				
Objectives	 Verification of proper work of modules G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRC, LRM, SCNGW and G2.RSVP-TE in case of SPC Call and FSC LSP setup: UNI LSP setup signalling through HEAD node and Node1 via G.UNI-RSVP UNI LSP setup signalling through Node2 and TAIL node via G.UNI-RSVP Call setup signalling through 2 G2.CCC instances (HEAD and TAIL node) and 2 G2.NCC instances (Node1 and Node2) INNI LSP setup signalling through 2 FSC nodes (Node1 and Node2) via G2.RSVP-TE TN equipments cross-connect configuration Data model information updating 				
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1				
Topology and DUT details	G2.CCC G.UNI-C RSVP	G2.NCC G.UNI-N RSVP RC G2 RSVP-TE	RC G2.NCC G2.NCC G.UNI-N RSVP	G2.CCC G.UNI-C RSVP	

Test de	Test description				
Step	Description	Outcome			
1.	G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 			
2.	Create Call from HEAD node G2.CCC	✓ Call is created and signalled up			
2.1.	HEAD node: Setup request is sent from G2.CCC to Node1	 ✓ UNI LSP is created and signalled up by G2.CCC ✓ Setup Indication is received from Node1 G2.NCC via G.UNI-RSVP signalling ✓ Setup Confirm is sent from G2.NCC to Node1 via G.UNI-RSVP signalling 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



		(0 !!: " !! 00 000
		✓ Call is "active" in G2.CCC
		✓ UNI LSP is "installed" in G.UNI-RSVP
		✓ Setup Request is sent from G2.NCC to Node2
		✓ Setup Indication is received from Node2 G2.NCC and
	Node1: Setup Request is	forwarded to HEAD node via G.UNI-RSVP signalling
	received from HEAD node	✓ Setup Confirm is received from HEAD node G2.NCC and
2.2.	G2.CCC via G.UNI-RSVP	forwarded by G2.NCC to Node2
	signalling	✓ Call is "active" in G2.NCC
	9 9	✓ UNI LSP is "installed" in G.UNI-RSVP
		✓ Recovery bundle is created in RC
		✓ Setup Request is forwarded to TAIL node via G.UNI-RSVP
		signalling
		✓ Setup Indication is received from TAIL node and forwarded
	Node2: Setup Request is	by G2.NCC to Node1
2.3.	received from Node1	✓ Setup Confirm is received from Node1 G2.NCC and
	G2.NCC	forwarded by G2.NCC to TAIL node
	32133	✓ Call is "active" in G2.NCC
		✓ UNI LSP is "installed" in G.UNI-RSVP
		✓ Recovery bundle is created in RC
		✓ Setup Indication is sent from G2.CCC to Node2 via G.UNI-
	TAIL node: Setup Request	RSVP signalling
2.4.	is received from Node2 G2.NCC via G.UNI-RSVP signalling	✓ Setup Confirm is received from Node2 G2.NCC
		✓ Call is "active" in G2.CCC
		✓ UNI LSP is "installed" in G.UNI-RSVP
	Croote INNI I CD from	
3.	Create INNI LSP from	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps
	Node1 RC	2.1., 2.2., 2.5. and 2.6.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC

Test status			
Passed			

5.3.1.4 Teardown of the one bidirectional single-domain FSC LSP by G2.CCC module

Test Card #	est Card # G ² MPLS-TC-3.4		
Test Card Name	Teardown of the one bidirectional single-domain FSC LSP by G2.CCC module	Authors	NXW, PSNC, UESSEX

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	control Plane functional	10010		
Objectives	 Verification of proper work of modules G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRC, LRM, SCNGW and G2.RSVP-TE in case of SPC Call and FSC LSP teardown: UNI LSP teardown signalling through HEAD node and Node1 via G.UNI-RSVP UNI LSP teardown signalling through Node2 and TAIL node via G.UNI-RSVP Call teardown signalling through 2 G2.CCC instances (HEAD and TAIL node) and 2 G2.NCC instances (Node1 and Node2) INNI LSP teardown signalling through 2 FSC nodes (Node1 and Node2) via G2.RSVP-TE TN equipments cross-connect configuration Data model information updating 			
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1, G ² MPLS-TC-3.3			
Topology and DUT details	G2.CCC G.UNI-C RSVP	G2.NCC G2.NCC RC G2 RSVP-TE	G2.NCC G2.NCC G2.NCC G2.NCC G2.NCC	G2.CCC G.UNI-C RSVP

Test des	cription	
Step	Description	Outcome
1.	G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent
2.	Create Call from HEAD node G2.CCC	✓ See G ² MPLS-TC-3.3:step 2.
3.	Create INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G2MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.
4.	Destroy Call from HEAD node G2.CCC	 ✓ Call is signalled down from HEAD node G2.CCC and destroyed
4.1.	HEAD node: Release Request is sent from G2.CCC to TAIL node via G.UNI-RSVP signalling	 ✓ Release Indication is received from Node1 G2.NCC ✓ Call is "idle" in G2.CCC and is destroyed

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



4.0	Node1: Release Request is received from HEAD node	 ✓ Release Request is forwarded by G2.NCC to Node2 G2.NCC ✓ Release Indication is received from Node2 G2.NCC and
4.2.	G2.CCC via G.UNI-RSVP	forwarded to HEAD node G2.CCC
	signalling	✓ Call is "idle" in G2.NCC and is destroyed
		✓ Recovery bundle is destroyed in RC
		✓ Release Request is forwarded by G2.NCC to TAIL node
		G2.CCC via G.UNI-RSVP signalling
	Node2: Release Request is	✓ Release Indication is received from TAIL node G2.CCC via
4.3.	received from Node1	G.UNI-RSVP signalling and forwarded by G2.NCC to
	G2.NCC	Node1
		✓ Call is "idle" in G2.NCC and is destroyed
		✓ Recovery bundle is destroyed in RC
	TAIL node: Release	✓ Release Indication is sent from G2.CCC to Node2 via
4.4.	Request is received from	G.UNI-RSVP signalling
'' ''	Node2 G2.NCC via G.UNI-	✓ Call is "idle" in G2.CCC and is destroyed
	RSVP signalling	54.1.10 1410 111 02.1000 4114 10 400110 you
5.	Destroy INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1:step 5.
	Nodel No	

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G.CCC and G2.NCC should be removed
- Post-conditions:
 - o new persistency files are created for G2.CCC and G2.NCC

Test status		
Passed		

5.3.1.5 Setup of one bidirectional single-domain FSC LSP by G.UNI-GW module

Test Card #	G ² MPLS-TC-3.5		
Test Card Name	Setup of one bidirectional single- domain FSC LSP by G.UNI-GW module	Authors	NXW, UESSEX, PSNC
Objectives	UNI LSP setup signalling thro	SVP-TE in ca ugh HEAD no ugh Node2 a 2 G.UNI-GW i	se of SPC Call and FSC LSP setup: ode and Node1 via G.UNI-RSVP nd TAIL node via G.UNI-RSVP instances, 2 G2.CCC instances

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



Roport on Ona Onn 20 t	L3 Control Flane functional tests			
	 INNI LSP setup signalling through 2 FSC nodes (Node1 and Node2) via G2.RSVP-TE TN equipments cross-connect configuration Data model information updating 			
Related Test Cards	G ² MPLS-TC-1.3, C	G ² MPLS-TC-3.1, G ² MPL	S-TC-3.3	
Topology and DUT details	G2.CCC G.UNI-C RSVP	G2.NCC G.UNI-N RSVP RC G2 RSVP-IE	RC G2.NCC G2.NCC G2.NCC G2.NCC	G.UNI-C RSVP

Test des	cription	
Step	Description	Outcome
1.	G.UNI-GWD, G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP- TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY, SCNGWD VTY, and G.UNI-GWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent
2.	Create Call from HEAD node G.UNI-GW	✓ Call is created and signalled up
2.1.	HEAD node: Call Create request is sent from G.UNI-GW to G2.CCC	 ✓ Setup Request is sent from G2.CCC to Node 1via G.UNI-RSVP signalling ✓ See G²MPLS-TC-3.3: step 2.1. ✓ Call is "installed" in G.UNI-GW
2.2.	Node1: Setup Request is received from HEAD node G2.CCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.3: step 2.2.
2.3.	Node2: Setup Request is received from Node1 G2.NCC	✓ See G ² MPLS-TC-3.3: step 2.3.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



2.4.	TAIL node: Setup Request is received from Node2 G2.NCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.3: step 2.4.	
3.	Create INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: step 2.1., 2.2., 2.5. and 2.6.	8

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC


Test status			
Passed			

5.3.1.6 Teardown of the one bidirectional single-domain FSC LSP by G.UNI-GW module

Test Card #	G ² MPLS-TC-3.6		
Test Card Name	Teardown of the one bidirectional single-domain FSC LSP by G.UNI-GW module	Authors	NXW, UESSEX, PSNC
Objectives	RC, TNRC, LRM, SCNGW and G2.R teardown: UNI LSP teardown signalling UNI LSP teardown signalling Call teardown signalling through (HEAD and TAIL node) and 2	•	
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1, G ² MPLS-TC-3.4, G ² MPLS-TC-3.5		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	cription	
Step	Description	Outcome
1.	G.UNI-GWD, G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP- TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY, SCNGWD VTY and G.UNI-GWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent
2.	Create Call from HEAD node G.UNI-GW	✓ See G ² MPLS-TC-3.5:step 2.
3.	Create INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.
4.	Destroy Call from HEAD node G.UNI-GW	 ✓ Call is signalled down from HEAD node G.UNI-GW and destroyed
4.1.	HEAD node: Call Destroy request is sent from G.UNI- GW to G2.CCC	 ✓ Release Request is sent from G2.CCC to TAIL node via G.UNI-RSVP signalling ✓ See G²MPLS-TC-3.4: step 4.1. ✓ Call is destroyed in G.UNI-GW
4.2.	Node1: Release Request is received from HEAD node G2.CCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.4: step 4.2.
4.3.	Node2: Release Request is received from Node1 G2.NCC	✓ See G ² MPLS-TC-3.4: step 4.3.
4.4.	TAIL node: Release Request is received from	✓ See G ² MPLS-TC-3.4: step 4.4.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	Node2 G2.NCC via G.UNI- RSVP signalling	
5.	Destroy INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1:step 5.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC


Test status		
Passed		

5.3.1.7 Setup of one bidirectional single-domain FSC LSP by Middleware WS-Agreement client

Test Card #	G ² MPLS-TC-3.7		
Test Card Name	Setup of one bidirectional single- domain FSC LSP by Middleware WS-Agreement client	Authors NXW, UESSEX, FHG, PSNC	
Objectives	Verification of proper work of modules RSVP, G2.NCC, RC, TNRC, LRM, SC FSC LSP setup: UNI LSP setup signalling through the setup si		2.RSVP-TE in case of SPC Call and ode and Node1 via G.UNI-RSVP and TAIL node via G.UNI-RSVP, 2 G.UNI-GW instances, 2 G2.CCC 2.NCC instances (Node1 and Node2) odes (Node1 and Node2) via
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1, G ² MPLS-TC-3.3, G ² MPLS-TC-3.5		
Topology and DUT details			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	WS-AG client, G.UNI-GWD, G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY, SCNGWD VTY, and G.UNI-GWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 		
2.	Create Call from WS-AG client	✓ Call is created and signalled up		
2.1.	WS-AG client: Call Create request is sent to HEAD node G.UNI-GW	✓ Connection to the web service server success and Call is created		
2.2.	HEAD node: Call Create request is received from WS-AG client	 ✓ Call Create request is sent from G.UNI-GW to G2.CCC ✓ See G²MPLS-TC-3.5: step 2.1. 		
2.3.	Node1: Setup Request is received from HEAD node G2.CCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.3: step 2.2.		
2.4.	Node2: Setup Request is received from Node1 G2.NCC	✓ See G ² MPLS-TC-3.3: step 2.3.		
2.5.	TAIL node: Setup Request	✓ See G ² MPLS-TC-3.3: step 2.4.		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	is received from Node2 G2.NCC via G.UNI-RSVP signalling	
3.	Create INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC


Test status		
Passed		

5.3.1.8 Teardown of the one bidirectional single-domain FSC LSP by Middleware WS-Agreement client

Test Card #	G ² MPLS-TC-3.8		
Test Card Name	Teardown of the one bidirectional single-domain FSC LSP by Middleware WS-Agreement client Authors NXW, UESSEX, FHG, PSNC		NXW, UESSEX, FHG, PSNC
Objectives	Verification of proper work of modules WS-AG client, G.UNI-GW, G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRC, LRM, SCNGW and G2.RSVP-TE in case of SPC Call and FSC LSP teardown: • UNI LSP teardown signalling through HEAD node and Node1 via G.UNI-RSVP • UNI LSP teardown signalling through Node2 and TAIL node via G.UNI-RSVP • Call teardown signalling through WS-AG client, 2 G.UNI-GW instances, 2 G2.CCC instances (HEAD and TAIL node) and 2 G2.NCC instances (Node1 and Node2) • INNI LSP teardown signalling through 2 FSC nodes (Node1 and Node2) via G2.RSVP-TE • TN equipments cross-connect configuration • Data model information updating		
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1, G ² MPLS-TC-3.4, G ² MPLS-TC-3.5, G ² MPLS-TC-3.7		
Topology and DUT details			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	G.UNI-GWD, G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP- TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY, SCNGWD VTY and G.UNI-GWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 		
2.	Create Call from WS-AG client	✓ See G ² MPLS-TC-3.7:step 2.		
3.	Create INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.		
4.	Destroy Call from WS-AG client	✓ Call is signalled down from WS-AG client and destroyed		
4.1.	WS-AG client: Call Destroy request is sent to HEAD node G.UNI-GW	✓ Connection to the web service server success and Call is destroyed		
4.2.	HEAD node: Call Destroy request is received from WS-AG client	 ✓ Call Destroy request is sent from G.UNI-GW to G2.CCC ✓ See G²MPLS-TC-3.6: step 4.1. 		
4.3.	Node1: Release Request is received from HEAD node G2.CCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.4: step 4.2.		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



4.4.	Node2: Release Request is received from Node1 G2.NCC	✓ See G ² MPLS-TC-3.4: step 4.3.
4.5.	TAIL node: Release Request is received from Node2 G2.NCC via G.UNI- RSVP signalling	✓ See G ² MPLS-TC-3.4: step 4.4.
5.	Destroy INNI LSP from Node1 RC	✓ See G ² MPLS-TC-3.1:step 5.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC

Test status		
Passed		

5.3.2 Inter-domain call signalling tests

In this section the results of the tests regarding the single-domain call signalling are presented. For this purpose $6 \, G^2 MPLS$ controllers have been deployed, in order to setup 2 different I-NNI domains (each one with 2 controllers) reachable by a G.UNI-GW client each.

In Figure 5.4 the logical topology of the test-bed for the inter-domain tests is described.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115







Figure 5.4: Logical topology of the inter-domain FSC test-bed for G²MPLS Call signalling tests.

5.3.2.1 Setup of one bidirectional inter-domain FSC LSP by G2.CCC

Test Card #	G ² MPLS-TC-4.1		
Test Card Name	Setup of one bidirectional inter- domain FSC LSP by G2.CCC	Authors	NXW
Objectives	 ENNI LSP setup signalling thr UNI LSP setup signalling thro Call setup signalling through 2 couples of G2.NCC instances 	and G2.RSVI ugh HEAD no rough Node2 ugh Node4 at 2 G2.CCC ins (Node1-Nod	P-TE in case of SPC Call and FSC ode and Node1 via G.UNI-RSVP and Node3 via G.ENNI-RSVP and TAIL node via G.UNI-RSVP of tances (HEAD and TAIL node) and 2

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test de	Test description			
Step	Description	Outcome		
1.	G2.CCC, G.UNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP-TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 		
2.	Create Call from HEAD node G2.CCC	✓ Call is created and signalled up		
2.1.	HEAD node: Setup request is sent from G2.CCC to Node1	✓ See G ² MPLS-TC-3.2: step 2.1.		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



2.2.	Node1: Setup Request is received from HEAD node G2.CCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.2: step 2.2.
2.3.	Node2: Setup Request is received from Node1 G2.NCC	 ✓ Setup Request is forwarded to Node3 via G.ENNI-RSVP signalling ✓ Setup Indication is received from Node3 via G.ENNI-RSVP signalling and forwarded by G2.NCC to Node1 ✓ Setup Confirm is received from Node1 G2.NCC and forwarded by G2.NCC to Node3 via G.ENNI-RSVP signalling ✓ Call is "active" in G2.NCC ✓ ENNI LSP is "installed" in G.ENNI-RSVP ✓ Recovery bundle is created in RC
2.4.	Node3: Setup Request is received from Node2 G2.NCC via G.ENNI-RSVP signalling	 ✓ Setup Request is forwarded from G2.NCC to Node4 ✓ Setup Indication is received from Node4 G2.NCC and forwarded to Node2 via G.ENNI-RSVP signalling ✓ Setup Confirm is received from Node2 via G.ENNI-RSVP and forwarded by G2.NCC to Node4 ✓ Call is "active" in G2.NCC ✓ ENNI LSP is "installed" in G.ENNI-RSVP ✓ Recovery bundle is created in RC
2.5.	Node4: Setup Request is received from Node3 G2.NCC	✓ See G ² MPLS-TC-3.2: step 2.3.
2.6.	TAIL node: Setup Request is received from Node2 G2.NCC via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.2: step 2.4.
3.	Create INNI LSP in Domain1 from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.
4.	Create INNI LSP in Domain2 from Node3 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - o the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - o new persistency files are created for G2.CCC and G2.NCC

Test status		
Passed		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115




5.3.2.2 Teardown of one bidirectional inter-domain FSC LSP by G2.CCC

Test Card #	G ² MPLS-TC-4.2		
Test Card Name	Teardown of the one bidirectional single-domain FSC LSP by G2.CCC		NXW
Objectives	 ENNI LSP teardown signalling UNI LSP teardown signalling Call teardown signalling through and 2 couples of G2.NCC ins Domain1 INNI LSP teardown Node2) via G2.RSVP-TE 	and G2.RSVF through HEAI g through Node through Node igh 2 G2.CCC tances (Node signalling thro signalling thro t configuration	P-TE in case of SPC Call and FSC D node and Node1 via G.UNI-RSVP de2 and Node3 via G.ENNI-RSVP e4 and TAIL node via G.UNI-RSVP c instances (HEAD and TAIL node) 1-Node2 and Node3-Node4) ough 2 FSC nodes (Node1 and
Related Test Cards	G ² MPLS-TC-1.3, G ² MPLS-TC-3.1, G ² MPLS-TC-3.3, G ² MPLS-TC-4.1		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	G2.CCC, G.UNI-RSVP, G.ENNI-RSVP, G2.NCC, RC, TNRCD, LRMD, SCNGWD and G2.RSVP- TED processes are running on nodes	 ✓ TNRCD VTY, LRMD VTY, G2.RSVP-TED VTY and SCNGWD VTY are accessible ✓ TE-link/CC/SCN-if bindings are consistent 		
2.	Create Call from HEAD node G2.CCC	✓ See G ² MPLS-TC-4.1:step 2.		
3.	Create INNI LSP in Domain1 from Node1 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.		
4.	Create INNI LSP in Domain3 from Node3 RC	✓ See G ² MPLS-TC-3.1 step 3. and G ² MPLS-TC-1.3: steps 2.1., 2.2., 2.5. and 2.6.		
5.	Destroy Call from HEAD node G2.CCC	 ✓ Call is signalled down from HEAD node G2.CCC and destroyed 		
5.1.	HEAD node: Release Request is sent from G2.CCC to TAIL node via G.UNI-RSVP signalling	✓ See G ² MPLS-TC-3.3: step 4.1.		
5.2.	Node1: Release Request is	✓ See G ² MPLS-TC-3.3: step 4.2.		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	received from HEAD node G2.CCC via G.UNI-RSVP signalling	
5.3.	Node2: Release Request is received from Node1 G2.NCC	 ✓ Release Request is forwarded by G2.NCC to Node3 via G.ENNI-RSVP signalling ✓ Release Indication is received from Node3 via G.ENNI-RSVP signalling and forwarded by G2.NCC to Node1 ✓ Call is "idle" in G2.NCC and is destroyed ✓ ENNI LSP is "down" and is destroyed ✓ Recovery bundle is destroyed in RC
5.4.	Node3: Release Request is received from Node2 via G.ENNI-RSVP signalling	 ✓ Release Request is forwarded by G2.NCC to Node4 G2.NCC ✓ Release Indication is received from Node4 G2.NCC and forwarded to Node2 via G.ENNI-RSVP signalling ✓ Call is "idle" in G2.NCC and is destroyed ✓ ENNI LSP is "down" and is destroyed ✓ Recovery bundle is destroyed in RC
5.5.	Node4: Release Request is received from Node1 G2.NCC	✓ See G ² MPLS-TC-3.3: step 4.3.
5.6.	TAIL node: Release Request is received from Node2 G2.NCC via G.UNI- RSVP signalling	✓ See G ² MPLS-TC-3.3: step 4.4.
6.	Destroy INNI LSP in Domain1 from Node1 RC	✓ See G ² MPLS-TC-3.1:step 5.
7.	Destroy INNI LSP in Domain2 from Node3 RC	✓ See G ² MPLS-TC-3.1:step 5.

Additional comments

- Pre-conditions:
 - o all needed resources by the LSP should be available and free on the equipments
 - the persistency files (*.pdb) related to and G:CCC and G2.NCC should be removed
- Post-conditions:
 - new persistency files are created for G2.CCC and G2.NCC

Test status		
Passed		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





5.4 G²MPLS routing tests

The G²MPLS routing advertisement tests have been executed in two separate sessions:

- G²MPLS single-domain routing tests
- G²MPLS Inter-domain routing tests

The single-domain tests have been used to verify the proper work and interaction of that modules involved in the single-domain routing (mainly G2.OSPF-INNI, G2.OSPF-UNI, LRM, SCNGW).

The inter-domain tests instead have been used to verify the proper operation and interaction of those modules involved in the multi-domain routing (mainly G2.OSPF-INNI, G2.OSPF-ENNI (referred also as ENNI-RC), G2.OSPF-UNI, LRM, SCNGW).

In the next two sessions the results of the two sessions of tests are shown.

The G²MPLS routing tests are divided also regarding network/grid functionalities:

- Routing network resources advertisement tests
- Routing Grid&Network resources advertisement tests

Routing network resources advertisement tests check the single-domain and multi-domain advertisement of router addresses, TE-links and TNA addresses. These test verify compatibility with standard GMPLS. Routing Grid&Network resources advertisement tests check the single-domain and multi-domain advertisement of Grid resources in parallel to network resource advertisement.

5.4.1 Single-domain routing test-cases

In this section are presented the results of the tests regarding the single-domain routing advertisement. As shown in Figure 5.5, in the test-bed there are 6 different G²MPLS controllers: 4 of them (Node 1, 2, 3 and 4) have been used as INNI nodes, and the other 2 as G.UNI-C clients.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115







Figure 5.5: Single-domain logical topology for routing tests.

5.4.1.1 Single node initialization test case

Test Card # G ² MPLS-TC-5.1			
Test Card Name I-NNI G2.OSPF-TE instance initialization		Authors	PSNC, NXW
Proper configuration of G2.OSPF-T		ID to G2.OSF	
Related Test Cards	None		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	scription	
Step	Description	Outcome
1.	Run TNRCD, LRMD and SCNGWD processes	✓ TNRCD VTY, LRMD VTY and SCNGWD VTY are accessible
2.	Run G2.OSPF-TED process	 ✓ G2.OSPF-TED is up and working There is G2.OSPF-TED process on the system processes list The configuration file was read successfully G2.OSPF-TED VTY is accessible ✓ There is no routing neighbours available ✓ The opaque capability is enabled
2.1.	I-NNI Router ID is loaded in G2.OSPF-TED from LRMD	✓ Router ID is available in G2.OSPF-TED VTY I-NNI instance
2.2.	Single-domain TE-link interfaces are loaded in G2.OSPF-TED from LRMD	 There are proper single-domain TE-link interfaces information available in G2.OSPF-TED VTY in I-NNI instance which are equivalent to information stored in LRMD TE-link identifiers (Link ID, Local/Remote Interface IP or Local/Remote Link ID), TE-link technology details (Link Type, Switching Capability) TE-link bandwidths (Max Bandwidth, Max Reservable Bandwidth, Unreserved Bandwidth) TE-link administration (TE Metric, SRLG, Administrative Group)
2.3.	Inter-domain TE-link interfaces are loaded in G2.OSPF-TED from LRMD	 There are proper inter-domain TE-link interfaces information available in G2.OSPF-TED VTY in I-NNI instance which are equivalent to information stored in LRMD TE-link identifiers (Link ID, Local/Remote Interface IP or Local/Remote Link ID, Local/Remote Node ID), TE-link technology details (Link Type, Switching Capability) TE-link bandwidths (Max Bandwidth, Max

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



		Reservable Bandwidth, Unreserved Bandwidth) TE-link administration (TE Metric, SRLG, Administrative Group)
2.4.	TNA addresses are loaded in G2.OSPF-TED from LRMD	 ✓ There are proper TNA addresses information available in G2.OSPF-TED VTY in G.UNI-N instance which are equivalent to information stored in LRMD TNA addresses Node ID hosting the TNA ✓ G.UNI-N router ID is read from G2.OSPF-TED configuration file

Additional comments

Single-domain TE-links are loaded if there are configured I-NNI TE-links in LRMD configuration. Inter-domain TE-links are loaded if there are configured E-NNI TE-links in LRMD configuration. TNA addresses are loaded if there are configured UNI TE-links in LRMD configuration. G.UNI-N router ID is loaded if there are configured UNI TE-links in LRMD configuration. If there is no G.UNI-Crouting node, then TNA address are not passed from G.UNI-N routing instance to G.I-NNI routing instance.


Test status		
Passed		

5.4.1.2 Network functionalities test case

Test Card #			
Test Card Name Distribution of TE information through the G.I-NNI interfaces		Authors	PSNC, NXW
Objectives	 checking TE database for neighbours list and states verifying incoming opaque list checking TNA address pushing from G.UNI-Crouting instance to G.I-NNI reinstance checking dynamic topology changes (e.g. bandwidth changes) 		I-Crouting instance to G.I-NNI routing
Related Test Cards	G ² MPLS-TC-5.1		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description			
Step	Description	Outcome		
1.	TNRCD, LRMD SCNGWD and G2.OSPF-TED processes are running on all G.I-NNI nodes	 ✓ TNRCD VTY, LRMD VTY, SCNGWD VTY and G2.OSPF- TED VTY are accessible ✓ See G2MPLS-TC-5.1 Step 1 and 2 		
2.	Routing information are advertised inside the local domain	✓ The same set of information about Router addresses, TE- links and TNAs is available in every node LSDB of the local domain		
2.1.	Routing adjacencies are established	 ✓ G2.OSPF-TED VTY presents a list of neighbour G.I-NNI routers ○ All neighbours are in 'full' state of OSPF Interface State Machine (ISM) 		
2.2.	I-NNI topology information are exchanged	 ✓ Router address is originated as TE opaque LSA ✓ Intra- and inter-domain TE-links information are originated as TE opaque LSAs ✓ TE opaque LSAs from other nodes containing Router addresses and TE-links are present in local node LSDB 		
2.3.	Change TE-link available bandwidth	✓ The value of TE-link available bandwidth is advertised and updated on every node LSDB in the network via flooding of an opaque LSA with new sequence number		
2.4.	Change TE-link metric	✓ The value of TE-link metric is advertised and updated on every node LSDB in the network via flooding of an opaque LSA with new sequence number		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



3.	Run G.UNI-Cnodes	 ✓ TNA addresses are originated by G.UNI-N instance in form of TE opaque LSAs ✓ TE opaque LSAs from other nodes containing TNA addresses are present in every node G.I-NNI LSDB ✓ TNA addresses are read by G.UNI-N instances from G.I-NNI LSDB
		✓ TNA address are send to G.UNI-C instances from G.UNI-N
		instances

Additional comments

After the test all nodes in the RA have the same and the up-to-date knowledge about Router addresses, TE-links and TNAs present in the domain. Each client node has list of all available TNA addresses in the domain. G.UNI-Chas no knowledge about Grid information yet.


Test status	
Passed	

5.4.1.3 Grid&Network functionalities test case

Test Card #	G ² MPLS-TC-5.3		
Test Card Name	Distribution of Grid information through the G.UNI and G.I-NNI interfaces	Authors	PSNC, NXW
Objectives	 validation of Grid information exchange between G.UNI and G.I-NNI instances checking the availability of Grid information at the network nodes checking the availability of Grid information at the client nodes checking dynamic grid information changes 		
Related Test Cards	G ² MPLS-TC-5.1, G ² MPLS-TC-5.2		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD SCNGWD and G2.OSPF-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, SCNGWD VTY and G2.OSPF- TED VTY are accessible ✓ See G2MPLS-TC-5.1 Step 1 and 2 			
2.	Routing information are advertised inside the local domain	 ✓ See G2MPLS-TC-5.2 Step 2 ✓ The same set of information about TE-links and TNAs is available in every node LSDB of the local domain 			
3.	Run G.UNI-Cnodes	 ✓ See G2MPLS-TC-5.2 Step 3 ✓ TNA addresses are originated by G2.OSPF-TED UNI-N instance in form of TE opaque LSAs ✓ TE opaque LSAs from other nodes containing TNA addresses are present in every node LSDB 			
4.	Configure Grid Site at one of G.UNI-C ID Name Provider Edge router ID Latitude and Longitude	 ✓ Grid Site TLV in Grid opaque LSA is originated from G.UNI-C to G.UNI-N ✓ The Grid Site TLV is pushed to G.I-NNI instance LSDB ✓ The Grid Site TLV is flooded to all domain nodes ✓ All G.UNI-N instances (except of the originating G.UNI-N) read the Grid Site TLV from G.I-NNI LSDB and send it to its G.UNI-C 			
5.	Configure Grid Service at the G.UNI-C	 ✓ Grid Service TLV in Grid opaque LSA is originated from G.UNI-C to G.UNI-N 			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	ID.	/ The Orid Coming TIVing at the OLDBUILDER 1975
	IDParent Site IDIPv4 addressService InfoStatus	 ✓ The Grid Service TLV is pushed to G.I-NNI instance LSDB ✓ The Grid Service TLV is flooded to all domain nodes ✓ All G.UNI-N instances (except of the originating G.UNI-N) read the Grid Service TLV from G.I-NNI LSDB and send it to its G.UNI-C
6.	Configure Grid Computing at the G.UNI-C ID Parent Site ID IPv4 Host Name LRMS Info Gatekeeper port Job Manager Data Dir Job States Job Stats Job Time Performance Job Time Policy Jobs Load Policy CE calendar	 ✓ Grid Computing TLV in Grid opaque LSA is originated from G.UNI-C to G.UNI-N ✓ The Grid Computing TLV is pushed to G.I-NNI instance LSDB ✓ The Grid Computing TLV is flooded to all domain nodes ✓ All G.UNI-N instances (except of the originating G.UNI-N) read the Grid Computing TLV from G.I-NNI LSDB and send it to its G.UNI-C
7.	Configure two Grid Sub- Clusters at the G.UNI-C ID Parent Site ID CPU Info OS Info Memory Info Software Package Sub-Cluster calendar	 ✓ Grid Sub-Cluster TLVs in Grid opaque LSA is originated from G.UNI-C to G.UNI-N ✓ The Grid Sub-Cluster TLVs are pushed to G.I-NNI instance LSDB ✓ The Grid Sub-Cluster TLVs are flooded to all domain nodes ✓ All G.UNI-N instances (except of the originating G.UNI-N) read the Grid Sub-Cluster TLVs from G.I-NNI LSDB and send them to its G.UNI-C
8.	Change Grid Computing information at G.UNI-C Job States Job Stats Job Time CE calendar	 ✓ The new values of Grid Computing are originated by G.UNI-C as an opaque LSA with new sequence number and updates the G.UNI-N LSDB ✓ G.UNI-N push the new Grid Computing TLV opaque LSA to G.I-NNI LSDB ✓ update on every node LSDB in the network via flooding of an opaque LSA with new sequence number ✓ G.UNI-N update the new Grid Computing TLV in its LSDB from G.I-NNI LSDB ✓ G.UNI-C send the new Grid Computing TLV opaque LSA to G.UNI-C
9.	Change Grid Sub-Cluster information at G.UNI-C • Sub-Cluster calendar	 ✓ The new values of Grid Sub-Cluster are originated by G.UNI-C as an opaque LSA with new sequence number and updates the G.UNI-N LSDB ✓ G.UNI-N push the new Grid Sub-Cluster TLV opaque LSA to G.I-NNI LSDB ✓ update on every node LSDB in the network via flooding of an opaque LSA with new sequence number ✓ G.UNI-N update the new Grid Sub-Cluster TLV in its LSDB from G.I-NNI LSDB

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115
Document Code: Phosphorus-WP2-D2.4



✓	G.UNI-C send the new Grid Sub-Cluster TLV opaque LSA
	to G.UNI-C

Additional comments

After the test all nodes in the RA and all client nodes have the same and up-to-date knowledge about Grid resources available in the domain.

Test status	
Passed	

5.4.2 Inter-domain routing test cases

In this section the results of the tests regarding the inter-domain routing advertisement are presented. For this purpose we need at least 6 G²MPLS controllers, to have 2 different INNI domains (each one with 2 controllers) reachable by a G.UNI-C each.

In Figure 5.4 the logical topology of the test-bed for the inter-domain tests is described.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115







Figure 5.6: Inter-domain logical topology for routing tests.

5.4.2.1 Network functionalities test case

Test Card #	G ² MPLS-TC-6.1		
Test Card Name	Routing information exchange between adjacent RAs	Authors	PSNC, NXW
Objectives	 Checking feed-up from I-NNI (RA level 0) to ENNI-RC (RA level 1) Checking routing information advertising between ENNI-RC (in RA level 1) Checking feed-down from ENNI-RC (RA level 1) to I-NNI (RA level 0) 		
Related Test Cards	G ² MPLS-TC-5.1, G ² MPLS-TC-5.2		

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115





Test des	Test description				
Step	Description	Outcome			
1.	TNRCD, LRMD SCNGWD and G2.OSPF-TED processes are running on all nodes	 ✓ TNRCD VTY, LRMD VTY, SCNGWD VTY and G2.OSPF-TED VTY are accessible ✓ See G2MPLS-TC-5.1 Step 1 and 2 ✓ G.E-NNI router ID is read from configuration file in case of RC 			
2.	Routing information are advertised inside the local domain	 ✓ See G2MPLS-TC-5.2 Step 2 and 3 ✓ The same set of information about Router addresses, TE-links and TNAs is available in every node LSDB of the local domain 			
3.	ENNI-RC appear in the domain	 ✓ Routing information are feed up to ENNI-RC ○ Inter-domain TE-links opaque LSAs are present in ENNI-RC LSDB ○ TNA addresses opaque LSAs are present in ENNI-RC LSDB 			
4.	Running the second domain with its own ENNI-RC	✓ Routing information are flooded to other ENNI-RC and populate in RA level 0 domain by feed down process			

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



4.1.	Routing information are advertised on RA level 1	✓ The same set of information about ENNI-RC addresses, inter-domain TE-links and TNAs is available in every node LSDB of the RA level 1 domain
4.2.	Routing adjacencies at level 1 are established	 ✓ G2.OSPF-TED VTY presents a list of neighbours E-NNI routers ✓ All neighbours are in 'full' state of OSPF Interface State Machine (ISM)
4.3.	E-NNI topology information are exchanged	 ✓ Inter-domain TE-links information are originated as TE opaque LSAs ✓ TE opaque LSAs from other nodes containing inter-domain TE-links are present in ENNI-RC LSDB ✓ TNA addresses are originated in form of TE opaque LSAs ✓ TE opaque LSAs from other nodes containing TNA addresses are present in ENNI-RC LSDB
4.4.	Routing information are feed down from RC	 ✓ Inter-domain TE-links opaque LSAs from other domains are present in RA level 0 domain nodes LSDB ✓ TNA addresses opaque LSAs are present in RA level 0 domain node LSDB
5.	Change inter-domain TE- link available bandwidth	 ✓ The new information about TE-link available bandwidth is updated in local domain, RA level 1 and in other RA level 0 domains ✓ new opaque LSA is flooded inside the RA level 0 local domain ✓ the LSA is feed up to local domain RC ✓ the LSA is advertised between ENNI-RCs (in RA level 1 domain) ✓ the LSA is feed down in ENNI-RC of the second domain ✓ the LSA is flooded inside the second RA level 0 domain
6.	Change inter-domain TE- link metric	 ✓ The new information about TE-link metric is updated in local domain, RA level 1 and in other RA level 0 domains ✓ new opaque LSA is flooded inside the RA level 0 local domain ✓ the LSA is feed up to local domain ENNI-RC ✓ the LSA is advertised between ENNI-RCs (in RA level 1 domain) ✓ the LSA is feed down in ENNI-RC of the second domain ✓ the LSA is flooded inside the second RA level 0 domain

Additional comments

After the test all nodes in every RA have the same and the newest knowledge about inter-domains TE-links and TNAs present in each domain. Each client node has list of all available TNA addresses in all domains.

Test status

Passed

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115

5.4.2.2 Grid&Network functionalities test case

Test Card #	G ² MPLS-TC-6.2		
Test Card Name	Grid information exchange betwee adjacent RAs	een Authors	PSNC, NXW
Objectives	 Checking Grid information feed-up from I-NNI (RA level 0) to ENNI-RC (RA level 1) Checking Grid information advertising between RC (in RA level 1) Checking Grid information feed-down from ENNI-RC (RA level 1) to I-NNI (RA level 0) 		
Related Test Cards	G ² MPLS-TC-5.1, G ² MPLS-TC-5	2, G ² MPLS-TC-5	3, G ² MPLS-TC-6.1
Topology and DUT details	G2 OSPF-UNI	OSPF-UNI G2 OSPF-INNI LRM	NODE 4 ENNI-RC G2 OSPF-INNI LRM
		F-UNI ENNI-F	NODE 2 G2 OSPF-INNI LRM

Test description		
Step	Description	Outcome
7.	TNRCD, LRMD SCNGWD	✓ TNRCD VTY, LRMD VTY, SCNGWD VTY and G2.OSPF-

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



	and G2.OSPF-TED	TED VTY are accessible
	processes are running on	✓ See G2MPLS-TC-5.1 Step 1 and 2
	all nodes	✓ G.E-NNI router ID is read from configuration file in case of
		ENNI-RC
	Grid information are	√ The same set of Grid information is available in every node
8.	advertised inside the local	LSDB of the local domain
	domain	✓ G ² MPLS-TC-5.3 Step 2, 3, 4, 5, 6 and 7
9.	ENNI-RC appear in the	✓ Grid information are feed up to ENNI-RC
	domain	 Grid opaque LSAs are present in RC LSDB
40	Running the second	✓ Gird information are flooded to other ENNI-RC and
10.	domain with its own ENNI-	populate in RA level 0 domain by feed down process
	RC Grid information are	✓ The same set of information about Grid information is
10.1.	advertised on RA level 1	available in every node LSDB of the RA level 1 domain
	advertised on KA lever i	✓ G2.OSPF-TED VTY presents a list of neighbours E-NNI
		routers
	Routing adjacencies at	✓ All neighbours are in 'full' state of OSPF Interface State
10.2.	level 1 are established	Machine (ISM)
		✓ See G2MPLS-TC-5.2 Step 2.1
		✓ See G2MPLS-TC-6.1 Step 4
		✓ Grid information are originated as Grid opaque LSAs
10.3.	E-NNI Grid information are	✓ Grid opaque LSAs from other nodes containing Grid
10.3.	exchanged	information from other domains are present in ENNI-RC
		LSDB
10.4.	Grid information are feed	✓ Grid opaque LSAs from other domains are present in RA
10.11	down from ENNI-RC	level 0 domain nodes LSDB
		✓ The new information about Grid Computing is updated in
	Change Grid Computing information at G.UNI-C • Job States • Job Stats • Job Time	local domain, RA level 1 and in other RA level 0 domains
		✓ new opaque LSA is flooded inside the RA level 0 local domain
11.		domain ✓ the LSA is feed up to local domain RC
11.		 ✓ the LSA is reed up to local domain RC ✓ the LSA is advertised between ENNI-RCs (in RA level 1
		domain)
	 CE calendar 	✓ the LSA is feed down in ENNI-RC of the second domain
		★ the LSA is flooded inside the second RA level 0 domain
		✓ The new information about Grid Sub-Cluster is updated in
		local domain, RA level 1 and in other RA level 0 domains
	Change Grid Sub Cluster	✓ new opaque LSA is flooded inside the RA level 0 local
	Change Grid Sub-Cluster information at G.UNI-C	domain
12.		√ the LSA is feed up to local domain ENNI-RC
	 Sub-Cluster calendar 	✓ the LSA is advertised between ENNI-RCs (in RA level 1)
		domain)
		✓ the LSA is feed down in ENNI-RC of the second domain
		✓ the LSA is flooded inside the second RA level 0 domain

Additional comments

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



After the test all nodes in every RA have the same and the newest knowledge about Grid resources present in each domain.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



6 Conclusions

This document reports the functional tests executed on the G²MPLS Control Plane built in the framework of Phosphorus WP2. Most of these tests comprised the single module and functionality verification, as well as the integrated operation of protocols and network controllers in meshed topologies. The software modules constituting the G²MPLS stack under test resulted from the integration of the delivered WP2 outputsat the passed milestones M2.1, M2.2, M2.3, M2.5.1 and M2.5.2.

This deliverable and its companion deliverable D2.5 on the preliminary G²MPLS Control Plane prototype contribute to the first official and public release of the G²MPLS Control Plane. They represent a first step of G²MPLS integration in the Phosphorus test-beds, an activity that will be progressed and finalized by WP6 team. In the PSNC and UESSEX local test-beds two switching technologies have been deployed, i.e. the fiber and the lambda switching, and proper mediation modules have been developed between the G²MPLS protocols and the Calient Diamond Wave Fibre Connect and the ADVA FSP-3000RE-II switches.

All the planned tests have been concluded successfully, both in the single-domain and in the inter-domain cases. They can be used as a test-suite for testing G²MPLS prototypes in different deployment scenarios., e.g. other G²MPLS test-beds installed in Phosphorus framework or externally. The same test-suite can help the validation phase of new developments on the stack, e.g. in case of addition of other mediation functions towards other equipments or switching technologies.

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



References 7

As explained in section 2, the references listed here are only those directly functional to this document. For a list of the references to standards appearing in this document, please point to [PH-WP2-D2.1], [PH-WP2-D2.2] and [PH-WP2-D2.7].

[PH-WP2-D2.1]	Phosphorus deliverable D2.1, "The Grid-GMPLS Control Plane architecture".
[PH-WP2-D2.2]	Phosphorus deliverable D2.2, "Routing and Signalling Extensions for the Grid-GMPLS Control
	Plane".
[PH-WP2-D2.3]	Phosphorus deliverable D2.3, "Grid-GMPLS high level system design".
[PH-WP2-D2.6]	Phosphorus deliverable D2.6, "Deployment models and solutions of the Grid-GMPLS Control
	Plane".
[PH-WP2-D2.7]	Phosphorus deliverable D2.7, "Grid-GMPLS network interfaces".
[PH-WP6-D6.1]	Phosphorus deliverable D6.1, "Test-bed design".
[PH-WP6-D6.6]	Phosphorus deliverable D6.6, "Plan of testing".

Project: Phosp Deliverable Number: D.2.4 Phosphorus 31/07/08 Date of Issue: EC Contract No.: 034115



8 Acronyms

CC Control Channel
CCC Client Call Controller

CP Control Plane

DWDM Dense Wavelength Division Multiplexing

E-NNI Exterior NNI

ENNI-RC E-NNI Routing Controller
ERO Explicit Route Object
FSC Fiber Switching Capability

G.E-NNI Grid E-NNI G.I-NNI Grid I-NNI

G2.CCC Grid-GMPLS CCC
G2.NCC Grid-GMPLS NCC
G2.OSPF-TE G2.OSPF-TE G2.OSPF-TE Daemon
G2.RSVP-TE G2.RSVP-TE G2.RSVP-TE Daemon

G²MPLS Grid-GMPLS (enhancements to GMPLS for Grid support)

GE Gigabit Ethernet
GMPLS Generalized MPLS

G.UNI Grid UNI

G.UNI-C G.UNI Client Site
G.UNI-GW G.UNI Gateway
G.UNI-GWD G.UNI-GW Daemon
G.UNI-N G.UNI Network Site

I-NNI Interior NNI
IP Internet Protocol

IPv4 Internet Protocol Version 4

LSA Local Area Network
LSA Link State Advertisement
LSC Lambda Switching Capability

LSDB Link State Database

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115



LSP Label Switched Path
LRM Link Resource Manager

LRMD LRM Daemon

MPLS Multi Protocol Label Switching

NCC Network Call Controller

NNI Network to Network Interface

OSPF Open Shortest Path First protocol

OSPF-TE OSPF with Traffic Engineering extensions

P2MP Point to Multi Point
RA Routing Area
RC Recovery Controller

RSVP Resource reSerVation Protocol

RSVP-TE RSVP with Traffic Engineering extensions

SCN Signalling Control Network

SCNGWSCN GatewaySCNGWDSCNGW DaemonTETraffic EngineeringTE-linkTraffic Engineering linkTL-1Transaction Language 1

TLV Type-Length-Value protocol fields

TN Transport Network

TNA Transport Network Address

TNRC Transport Network Resource Controller

TNRC Daemon
TNRC AP TNRC Abstract Part
TNRC SP TNRC Specific Part
TP Transport Plane

UNI User to Network Interface

VLAN Virtual LAN

VPN Virtual Private Network
VTY Virtual TeletYpe interface
WAN Wide Area Network

WP Work Package

WS-AG WebService Agreement

<END-OF-DOCUMENT>

Project: Phosphorus
Deliverable Number: D.2.4
Date of Issue: 31/07/08
EC Contract No.: 034115